Bill of Quantities (BOQ)

Badera utter tarfa nali nirman hirajung sadak,Badera chowk dekhi utter nala nirman,Badera chowk dekhi utter nala, Bijaypur dekhi ghiu dall jane sadak starunnati, dhanchyal dekhi sundarbasti jodne adhuro sadak

IFB No.: 80547403/14.SUN/NCB/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Necessary Lab Test Work for official purpose.(Regular reports for Quality Assurance of work done shall be under Contractor responsibility)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	37,000.00 Thirty-seven thousand rupees only.	37,000.00 Thirty-seven thousand rupees only.
PS.3	Provide and Installed Project Sign boards	PS	1.00	6,000.00 Six thousand rupees only.	6,000.00 Six thousand rupees only.
PS.4	Other Unseen Miscellenous Works as per approval. (The payment of this item will be done according to submitted original copy ofrelated invoices.)	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
	Total provisional sums				1,08,000.00 One lakh eight thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications. @ Depth upto 3m (mechanical means)	Cubic Meter	175.78			
1.2	Scarifying the existing road surface by mechanical means to a depth of 50 mm and disposal of scarified material with all lifts and leads as per Drawing and Technical Specification.	SQM	1,046.20			

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment)	Cubic Meter	156.93			
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones on prepared surface as per Drawing and Technical Specifications.	Cubic Meter	159.61			
1.5	Providing Brick Bat soiling filling in foundation of Drain & structure as per drawings, specification and instruction of the consultant/Engineer, all complete	Cubic Meter	12.95			
1.6	Providing and laying of PCC (1:3:6) in foundation all complete with fair finish Formwork as per Drawing and Technical Specifications	Cubic Meter	153.31			
1.7	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes, with fair finish Formwork etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cubic Meter	79.56			
1.8	Providing and Laying RCC 600mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Running Meter	5.00			
1.9	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters (By Mechanical Means)- (iii.B) Rubble stone masonry in cement mortar	Cubic Meter	8.28			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 and providing necessary 100 mm dia HDPE pipes if required for weep holes etc all complete as per Drawing and Technical Specifications	Cubic Meter	24.50			
1.11	Providing and Pointing with cement mortar 1:3 on masonry work in structure as per Technical Specifications	SQM	70.00			
1.12	Providing and laying HDPE pipes (dia 250mm-160mm) for drainage outlet ,subsoil drain including perforations and joining ,all complete as per drawing and instruction by Engineer	Running Meter	18.00			

Total Item Price	
VAT (13.00%)	
Grand Total	