Bill of Quantities (BOQ)

व्यवसायिक कृषिद्वारा खाद्य सुरक्षा सुनिश्चितता तथा आय आर्जन सुधार कार्यक्रम / आर्थिक सामाजिक विभेदमा परेका वर्ग उथानका लागि व्यवसायिक कृषिद्वारा खाद्य सुरक्षा सुनिश्चितता तथा आय आर्जनसुधार कार्यक्रम

IFB No.: 801054702/RAM/NCB/WORKS/05/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	"Insurances for the loss of damage to works, plant, material, equipment, property and personal injury or death and as stipulated in contract Data "	PS	1.00	99,000.00 Ninety-nine thousand rupees only.	99,000.00 Ninety-nine thousand rupees only.
PS.2	"Laboratary Tests as directed by site incharge "	PS	1.00	49,000.00 Forty-nine thousand rupees only.	49,000.00 Forty-nine thousand rupees only.
	Total provisional sums				1,48,000.00 One lakh forty-eight thousand rupees only.

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	"Preparation and drilling of bore holes of different diameters using machine including installation of pipes, pumping of water all complete and as directed by site incharge "	rm	3,515.00			
1.2	Supplying, laying, transportation and jointing of 4 inch dia GI pipe including testing and commissioning all complete as per specification and as directed by site incharge	rm	23.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	"Supply, laying, transportation and jointing of 4 inch dia MS threaded Medium class 4 mm thickness pipe, unit weight 12 kg per metre including testing and commissioning all complete as per specification and as directed by site incharge "	kg	3,033.33			
1.4	"Supplying, laying, transportation and jointing of 4 inch dia UPVC pipe of 10 kg/cm2 including testing and commissioning all complete as per specification and as directed by site incharge "	rm	3,255.00			
1.5	"Supplying, transportation and laying Bentonite powder all complete as per specification/ as directed by site incharge "	kg	1,050.00			
1.6	"Supplying, transportation and laying chips all complete as per specification/ as directed by site incharge "	cum	109.20			
1.7	"Supplying, laying, transportation and jointing of 4 no head hund pump complete set of including testing and commissioning all complete as per specification and as directed by site incharge "	no	21.00			
1.8	"Compressor Charging all complete as per specification / as directed by site incharge "	Hours	210.00			
1.9	Site clearance woks at each sites	LS	21.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	"Supplying, laying, transportation and installation of 3 HP submersible motor set of approved quality, including testing and commissioning all complete as per specification / as directed by site incharge "	set	10.00			
1.11	"Supplying, laying, transportation and installation of 2 HP submersible motor set of approved quality including testing and commissioning all complete as per specification / as directed by site incharge "	set	13.00			
1.12	"Supplying, laying, transportation and installation of 5 HP electric panel board set of approved quality including testing and commissioning all complete as per specification / as directed by site incharge "	set	10.00			
1.13	"Supplying, laying, transportation and installation of 3 HP electric panel board set of approved quality including testing and commissioning all complete as per specification / as directed by site incharge "	set	13.00			
1.14	"Supplying, laying, transportation and installation of 6 mm flat submersible cable including testing and commissioning all complete as per specification / as directed by site incharge "	rm	1,050.00			
1.15	"Supplying, laying, transportation and installation of 6 mm GI tochan wire including testing and commissioning all complete as per specification / as directed by site incharge "	rm	1,050.00			
1.16	"Supplying, laying, transportation and installation of complete flange set as rquired all complete as per specification / as directed by site incharge "	set	42.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.17	"Supplying, laying, transportation and installation of complete 2 inch dia 12 inch long GI nipple all complete as per specification / as directed by site incharge "	no	21.00			
1.18	"Supplying, laying, transportation and installation/jointing of 2 inch dia HDPE pipe (PN 10) including testing and commissioning all complete as per specification / as directed by site incharge "	rm	798.00			
1.19	"Supplying, laying, transportation, and lowering of pump at each site as required on site, all complete as directed by site incharge "	LS	21.00			
1.20	"Supplying, laying, transportation and installation/jointing of 2 inch dia socket including testing and comissioning all complete as per specification / as directed by site incharge "	no	68.00			
1.21	"Project information board of size 1.2 m X 1.5 feet m "	no	10.00			

Total Item Price	
VAT (13.00%)	
Grand Total	