Bill of Quantities (BOQ)

Upgrading of Gagre Bhanjyang Jitpur Soyak Belase Road from Kharayo Danda to Mai khola Section, Ilam

IFB No.: 3370103011/IDOILAM/NCB/W/09/83/84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for loss or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data and technical specifiation (Cl. 19 of CoC)	PS.	1.00	85,000.00 Eighty-five thousand rupees only.	85,000.00 Eighty-five thousand rupees only.
PS.2	Carrying out laboratory and field tests on materials and completed works, as required and as directed by the Engineer, including all necessary arrangements and incidental works, complete.	PS.	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.3	Providing, writing and installation of the project information board as per the Standard Specifications and approved drawings and as instructed by the Engineer.	PS.	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				1,27,000.00 One lakh twenty-seven thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Road way Excavation in all types of soil including ordinary rock as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.by Mechanical Means	Cum.	1,381.9846			
1.2	Roadway Excavation in hard rock with rock breakers, including breaking rock, lifts and lead for disposal as per Drawing and Technical Specifications Mechanical method, lead upto 30 m	Cum.	26.6254			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum.	91.84			
1.4	Providing and laying of Reinforced Cement Concrete in Foundation complete INCLUDING FORMWORK as per Drawing and Technical Specifications. RCC Grade M 20	Cum.	333.50			
1.5	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification.	MT	17.18822			

Total Item Price	
VAT (13.00%)	
Grand Total	