Bill of Quantities (BOQ)

Construction of Senior Staff Quarter of Nirmal Lama Polytechnic Institute

IFB No.: CTEVT/NLPI/083/84/NCB/Civil-01

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Provide Insurance to permanent works and construction equipments and angainst to work force and engineer's staffs including third party insurance all complete.	PS	1.00	1,00,000.00 One lakh rupees only.	1,00,000.00 One lakh rupees only.
PS.2	Provide Laboratory test for materials and concrete cube tests of required number for the period of contract as per specification and instruction of site incharge.	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
PS.3	Provide and maintain all the lights, guards,.fencing netting warning signs project sign board and watching for the protection of the works for the safety and convinces of the public or other as per contract specification and instruction of site engineer.	JOB	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.4	Preparation of As Built Drawings after complection of the works all complete.	JOB	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				1,80,000.00 One lakh eighty thousand rupees only.

Vocational college construction work
CPV: 45214310-6 - Vocational college construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Site preparation work including cutting of vegetation, surface dressing and site clearance.	Sqm	503.14			
1.2	EARTHWORKS IN EXCAVATION: Earth work in excavation in foundation including lift up to 2.5m timbering, pumping out water from the foundation trench, stacking the soil 1m. minimum from the edge of the foundation trench, back filling the excavated soil with clean and grub of soil up to a lead of 30m. as per drawing, specification and instruction of the engineer, all complete.	Cum	506.83			

Vocational college construction work
CPV: 45214310-6 - Vocational college construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	EARTHFILLING: Earth work in filling in foundation, floor etc. shall be done with good excavated soil in the floor with proper ramming in 20cm layers ,after sprinkling water and consolidating to 15 cm layer, as per drawing, specification and instruction of the engineer, all complete.	Cum	241.05			
1.4	EARTHFILLING IN ROOM AREAS: Earth work in filling in floor etc. shall be done with good imported soil/sand in the floor with proper ramming in 20cm layers ,after sprinkling water and consolidating to 15 cm layer , as per drawing, specification and instruction of the engineer, all complete.	Cum	156.38			
1.6	FLAT BRICK SOLING: Providing and laying, dry brick soling in floor with first class chimney made bricks complete to level including sand filling on joints, as per drawing, specification and instruction of engineer, all complete.	Cum	676.10			
1.7	PCC WORKS: Providing and laying, plain cement concrete (1:3:6) in foundation and floor with cement, sand and stone ballast including mixing, laying in panels providing proper slopes, lines and level and curing, as per drawing, specification and instructions of engineer, all complete.	Cum	36.89			
1.8	RCC WORKS: Providing and laying, plain cement concrete M20 for R.C.C. columns, beams, slabs, lintels, associated cornice columns footings, and all kinds of R.C.C. works with cement,sand and stone ballast including mixing, laying, curing finishing etc. excluding reinforcement, centering and shuttering as per drawings, specification and instruction of the engineer, all complete.	Cum	242.15			
1.29	STEEL REINFORCEMENT: Providing and laying, steel reinforcement bar including straightening, cleaning,cutting, bending, binding with 20 SWG annealed tying wire and fixing in positions as per drawing, specifications and instructions of the engineer, all complete.	MT	35.26			

Vocational college construction work CPV: 45214310-6 - Vocational college construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.30	FORMWORKS: Providing and laying, centering and shuttering with approved materials for all kinds RCC works including all necessary mild steel propping, scaffolding, staging, supporting, etc. all complete net as per drawings, specifications and instructions of the engineer, all complete.	Sqm	1,659.23			
1.31	BRICKWORK IN SUBSTRUCTURE: Providing and laying, brickwork in foundation with approved quality first class chimney made brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete in all types and thickness of walls, columns, etc. as per drawings, specification and instruction of engineer, all complete.	Cum	88.91			
1.32	BRICKWORK IN SUPERSTRUCTURE: Providing and laying, brick work (1: 6) in superstructure with approved quality first class brick in perfect line and level, finished including wetting the bricks, packing the joints and curing the work and necessary scaffolding, complete in all types and thickness of walls, associated cornices, columns, etc. as per drawings, specification and instruction of engineer, all complete.	Cum	137.58			
1.33	Providing & building Brick Masonry 115mm Thk. using bricks of first class chimney made as per NS 1/2035 in Cement mortar (1:4) in superstructure to its true line & level in cement mortar proportion as specified in all shapes, size, at all heights, depths, leads & locations etc. complete including or provision of RCC horizontal stiffeners of 100mm thk in 1:2:4 proportions (Cement : Fine aggregates: Coarse aggregates) at every 10th coarse by using 4 nos. of 8mm dia tor steel reinforcement longitudinal bars and 6mm dia MS reinforcement bars 250mm centre to centre at right angles to longitudinal steel including shuttering, formwork where necessary, as directed by EIC and paid accordingly. The rate shall also include for cleaning of surface, hacking of RCC surface in contact with brickwork, raking of joints, providing, erecting, & dismantling steel scaffolding , curing for 10 days etc. compete as per the drgs., details & specifications and to the satisfaction of Engineer-In-Charge.	Sqm	630.84			

Vocational college construction work
CPV: 45214310-6 - Vocational college construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.34	Providing and laying, cement sand plastering on floor, wall, ceiling, skirting, dado, cornices, etc. of good finish, including raking the joints, cleaning and wetting the surface and curing the works all complete, as per drawing, specification and instruction of engineer, all complete. - 20mm thick plaster (1:6 c/m)	Sqm	1,499.19			
1.35	12.5mm thick plaster (1:4 c/m)	Sqm	1,853.86			
1.36	Providing and applying, inside and outside painting with approved color and paints with two coats of primer to give uniform color after rendering surface clean with sandpapering as per drawing, specifications and instruction of the engineer, all complete - TWO COAT WEATHER COAT PAINT OVER ONE COAT PRIMER: Providing and applying two coats of weather coat paint over one coat of primer including scraping, surface preparation, scaffolding etc., all complete as per specifications, instructions and as approved by site incharge.	Sqm	854.39			
1.37	TWO COAT DISTEMPER PAINT OVER PRIMER COAT: Providing and applying two coat distemper paint over primer coat including scraping, surface preparation, scaffolding etc., all complete as per specifications, instructions and as approved by site incharge.	Sqm	2,498.66			
1.38	Providing and laying screeding (38mm thick) with 1:2:4 concrete mix on proper slope after scraping, cleaning and watering the old surface as per drawing, specification and instruction of engineer, all complete.	Cum	39.57			
1.39	Providing and laying, 3 mm thick cement sand punning (1:1) on floor, skirting , dado etc. including cleaning and wetting surface, mixing, laying and rubbing with steel trowel to a hard, smooth and shining surface and curing for a quality finish as per drawing, specification instruction of engineer, all complete.	Sqm	1,076.90			
1.40	Supplying and Installation of UPVC Profile Sliding Windows Frame 80*50mm White Colour,Sliding Window sash 55*36mm with galvanized steel Reinforcement of 1.5mm,5mm thick Clear Glass, insect Net,Pattented standard hardware Like:roller,gasket,brush all complete.	Sqm	78.45			

Vocational college construction work
CPV: 45214310-6 - Vocational college construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.41	Supplying and Installation of UPVC Profile Slidingliding doors Frame 80*50mm White Colour, sash 55*36mm with galvanized steel Reinforcement of 1.5mm, 5mm thick Clear Glass, insect Net, Pattented standard hardware Like:roller,gasket,brush all complete.	Sqm	84.76			
1.42	Supplying and installation of UPVC profile double door with full panel frame 60 x 60 mm, sash 60 x 104 mm, white colour, Pattented standard hardware Like:roller,gasket,brush all complete as per specification of Korean Standard.	Sqm	71.65			
1.43	Providing and laying, 16 mm. thick plain Marblestone in Staircase and kitchen slab, dado, skirting, etc. laid with 20mm thick Cement Sand mortar (1:2) in proper slope for draining wash water, joint not exceeding 3 mm. and pointed with White Cement slurry, grinding, polishing to smooth glazed surface and waxed finish in floor, of the approved colour and quality, as per drawing, specification and instruction of engineer, all complete.	Sqm	57.50			
1.44	Providing & fixing in toilets non slippery ceramic tiles of either 12"x12" or 16"x16" approximately of selected colour pattern and specified makes layed with straight close joints. The area of existing floor slab of toilets shall be cleaned and properly waterproofed before laying the tiles, the tiles shall be laid with required bedding materials of cement and sand mix. The all joints shall be filled in with matching colour ready made fillers of approved brand, the tile floor shall be protected without allowing any damages to finish. Complete with cleaning / washing etc. at final stage.	Sqm	207.06			
1.45	Providing & fixing glazed wall tiles of approved colour pattern and specified make in 12'x18" or 12"x10" in size including cement plaster base treated with required water proofing at atleast up to 18" high wall portion above floor level on all sides and 12mm thk. plain cement paste as bonding material. The tiles shall be laid in straights joints filled with matching colour ready fillers of approved make complete with plumb level and cleaning, washing the total area.	Sqm	226.75			

Vocational college construction work
CPV: 45214310-6 - Vocational college construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.46	Supplying & fixing railing work of 38 mm Ø stainless steel pipe post @ 2.0 m., 38 mm Ø stainless steel pipe hand rail with two rows of 25 mm Ø stainless steel pipe in between ground & hand rail, having railing height 2.5' -3' as per drawing, specification and instruction of engineer, all complete.	RM	35.48			

Plumbing and sanitary works
CPV: 45330000-9 - Plumbing and sanitary works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.1	Supplying & fixing white glazed porcelain clay one piece commode with 'P" and 'S" trap and slow falling seat cover complete set.	Set	8.00			
2.3	Providing and fixing in position Hand Wash Basin (W.B.) Oval shape of Parryware Standard of size 22" x 16" with 1/2 " dia C.P. single lever hot and cold mixer 11/4 " dia C.P. waste coupling with C.P. chain and rubber plug, 11/4" dia P. V. C. bottle trap heavy quality, 1/2" dia C.P. angle stop-cock 2 nos, with C.P. cap and 1/2" dia C.P. connection to waste line and water lines all complete and ready for operation (all C.P. fittings of Parry, Jaquar or equivalent of apparoed make)	Set	8.00			
2.4	Supplying & fixing in position heavy quality stainless steel sink with single bowl and drain board of 304 grade steel (Parryware Cat. No. 8531 or equivalent) with 1 1/2" dia. Waste couplin and bottle trap, 1/2" dia. C. P. single lever sink mizer with 2 nos. 1/2" dia. C. P. angle stop cock, connecting pipes etc. all complete and ready for use. (All C. P. fittings of American Standard or Jaquar or Parryware)	No.	8.00			
2.5	Supplying and fixing in position shower set compromising of C. P. hot & cold mixer with provision for shower and 115 mm long bend & wall flange and over head shower of Jaquar Cat NO. 491 set and mixer Cat no. 273 or equivalent	Set	8.00			
2.6	CP Soap Dish	No.	8.00			

Plumbing and sanitary works CPV: 45330000-9 - Plumbing and sanitary works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.7	15mm CP Commode Spray	No.	8.00			
2.8	20x600mm CP Towel Rail	No.	8.00			
2.9	Stainless steel towel rod 1.5X45cm	No.	8.00			
2.10	CP Robe Hook	No.	8.00			
2.11	5 mm thick looking mirror of approved make with CP mirror screws and clips. 3'x2' size	No.	8.00			
2.12	PVC floor trap	No.	24.00			
2.13	CP Cocroach trap	No.	24.00			
2.14	110mm Rain Inlet with cover	No.	5.00			
2.15	110mm PVC Cowl Vent	No.	5.00			
2.16	75mm PVC Cowl Vent	No.	4.00			
2.17	B. WATER SUPPLY INSTALLATION - CPVC pipes SDR-11 including MS clamps and brackets, nails and hooks, and all necessary CPVC/Brass specials required for complete installation, cutting, jointing, sealing of joints etc, installation of pipes and specials including making holes and cutting grooves on walls or floor and repairing the same to its original finish. Pipes to be installed on trenches or walls or floor or duct as per drawings, specifications and instructions, cleaning of the system, testing and ready for operation. The rate shall include for all labour and materials required. The measurement shall be done for running feet, fittings etc not payable seperately. - 32 mm	R.ft.	160.00			
2.18	- 25 mm	R.ft.	320.00			
2.19	- 20 mm	R.ft.	720.00			

Plumbing and sanitary works CPV: 45330000-9 - Plumbing and sanitary works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.20	CPVC Ball Valve - 32 mm dia.	No.	2.00			
2.21	- 25 mm dia.	No.	5.00			
2.22	- 20 mm dia.	No.	16.00			
2.23	2000 litres capacity Stainless steel cyllindrical vertical water storage roof tank complete with inlet, outlet, washout, overflow and inter-connection provisions	No.	1.00			
2.24	Pedrollo or equivalent brand electric pump with motor (approx.2 HP) of capacity 40 lpm at 32.5 M head including pipe connections, foundation, electrification, starter, testing and ready for operation (including one set stand-by).	Set	1.00			
2.25	C. SEWER, VENT, RAIN AND WASTE WATER INSTALLATION Panchakanya or approved brand PVC pipes including cutting, jointing, sealing with rubber washer and solvent cement and all necessary Supreme or Prince or Panchakanya brand rubber ringed moulded fittings such as Tees, Y-Tees, Bends (with or without doors), Reducers, Couplers, connector pieces, offsets etc. for complete installation, PVC clamps, nails and hooks. Installation of pipes and specials including making holes on walls or floor and repairing the same to its original finish, excavation and backfill (compaction as per civil works specifications) in any type of soil. Pipes to be installed on trenches or walls or floor or hung to ceilings as per drawings, specifications and instructions, cleaning of the system, testing and ready for operation. The rate shall include for all labour and materials required. The measurement shall be done for running metre, fittings etc not payable seperately. - 110 mm ED 4 kg/cm2	R.ft.	250.00			
2.26	- 75 mm ED 4 kg/cm2	R.ft.	208.00			
2.27	- 50 mm ED 6 kg/cm2	R.ft.	190.00			
2.28	Astral DWV pipes with fittings - 110 mm ED SN-4	R.ft.	300.00			

Plumbing and sanitary works CPV: 45330000-9 - Plumbing and sanitary works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.29	- 75 mm ED SN-4	R.ft.	15.00			

Electrical wiring and fitting work CPV: 45311000-0 - Electrical wiring and fitting work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.1	Main Distribution Board: Main Panel Board-double door type with locking arrangement with 2 coat of red oxide metal prime & 3 stage quality paint before final coat of enamel paint (phases, Neutral link, earth link) TPNE copper busbar including necessary accessories for internal wiring at the board all complete) 250/300AMP 12"×52"×62" size Panel box	Set	1.00			
3.2	Kilo watt hour energy meter 3 phase direct	Set	1.00			
3.3	0-500 volt meter	Set	1.00			
3.4	60/100 Amp meter	Set	1.00			
3.5	Panel Indicator	Set	3.00			
3.6	2 AMP glass fuse with holder 12mm size	Set	1.00			
3.7	Voltmeter selector switch	Set	1.00			
3.8	60/100 AMP C.T. Coil per set 3 pcs	Set	1.00			
3.9	150-200AMP C.T. coil 3 pcs per set	Set	1.00			
3.10	250AMP TP MCCB 36KA	Set	1.00			
3.11	16AMP- 63AMP TP MCCB 16KA	Set	1.00			

Electrical wiring and fitting work
CPV: 45311000-0 - Electrical wiring and fitting work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
3.12	Floor DB_Ground and first floor with complete set as follows; 40 A, TP MCCB, 18 K, Schneider,ABB, GE,Mitsubishi (SW series) no 1, 16 amp SP MCB (10kA) Schneider/GE/ABB/ no 9, 6 amp SP MCB (10kA) Schneider/GE/ABB/ no 3, busbar of 25mm x 3 mm size no 4, 20 x 3 size earth bus bar no 1	set	2.00			
3.13	Room DB (16 amp DP MCB (10kA) Schneider/GE/ABB/ -1; 16 A, single pole MCB (10kA) Schneider/GE/ABB/-1; 6 A, single pole MCB (10kA) Schneider/GE/ABB/ -1)	set	8.00			
3.14	Main Cable Supply, Delivery, Installation & commission of mains cable from transformer/Generator/to control panel/DB's etc as per drawing and specification including cable shoe at both ends. Note: cost of this item or work shall not include cost of the cable trench & cost of the cable tray. (Prakash cable, Trishakti cables, Pioneer cables, Premiere Cables, Nepal Cable, or any approved manufacturers by Dept of Housing) 3.5C , 70 sq.mm AL Unarm Cable	rm	43.00			
3.15	3.5C , 25 sq.mm CU Unarm Cable	rm	70.00			
3.16	3.5C , 16 sq.mm Cu Unarm Cable	rm	95.00			
3.17	3.5C , 10 sq.mm Cu Unarm Cable	rm	121.00			
3.18	2 x 6 sq.mm Cu+ 1 x 2.5 sq mm	rm	187.00			
3.19	2 x 4 sq.mm Cu+ 1 x 1.5 sq mm	rm	158.00			
3.20	2 x 2.5 sq.mm Cu	rm	79.00			
3.21	Supply and installtion of cable tray/ cable riser made of 3/4" MS angle with strips spacers at 8" distance, down rod all complette with epoxy (doubel quote) paint with following width sizes; 6 " size	rm	21.00			

Electrical wiring and fitting work
CPV: 45311000-0 - Electrical wiring and fitting work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
3.22	Supply and installtion of cable tray/ cable riser made of 3/4" MS angle with strips spacers at 8" distance, down rod all complette with epoxy (doubel quote) paint with following width sizes; 12 " size	rm	16.00			
3.23	Supply and installation of light point wiring from Room DB/ Junction,Switch Box to various points with 2 x 2.5 sq mm PVC insulated multi stranded copper wire through 20 mm dia MS conduit directly from the SDB's, concealed via switch as per drawing and specification including the cost of junction box and switch .[Note : A light fixture along with its switch and juction shall be counted as a point and the average rm per point is 8 rm from SDB to point]	pts	111.00			
3.24	Supply and installation of light fixtures with required accessories and fiitings, complete set as specification and instruction. 8" dia ceilling dome with GLS	nos	22.00			
3.25	1x 11 W CFL in Wall light	nos	56.00			
3.26	2 x 25 W Candle light in Bathroom Mirror Light	nos	16.00			
3.27	1x 60 W GLS in Bulk Head Light (Wall)	nos	7.00			
3.28	1 x 40 W Normal Box type Fluo Tube with cu ballast	nos	8.00			
3.29	1 x 1/18 W PLT in Globe (street light) Outdoor Light	nos	2.00			
3.30	Supply & Installtion of switch sockets (MAKE : Clipsal/ Orange or eqvt) 1 gang 1 way	nos	8.00			
3.31	2 gang 1 way	nos	8.00			
3.32	3 gang 1 way	nos	32.00			

Electrical wiring and fitting work
CPV: 45311000-0 - Electrical wiring and fitting work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
3.33	4 gang 1 way	nos	8.00			
3.34	6 gang 1 way	nos	2.00			
3.35	1 gang 2 way	nos	10.00			
3.36	2 gang 2 way	nos	2.00			
3.37	Supply and installation of Two way control light point wiring directly from Room DB to various points with 3 x 2.5 sq mm multistranded insulated copper FR cable through 20 mm internal dia HDPE conduit directly from SDB concealed via switch as per drawing and specification including the cost of junction metal box and 2 nos of switches .[Note : A light point along with its switch and juction shall be counted as a point and the average rm per point is 14 rm from DB to point]	pts.	8.00			
3.38	Supply and installation of 5 A , 2 pin socket point wiring from Room DB with 2 x 2.5 +1 x 1 sq mm pvc insulated multi stranded copper wires through 20 mm internal dia Hard conduit including proper Heavy gause metal box concealed from DB to various points through pool boxes wherever required (no junction boxes shall be used) as per the drawing, as per drawing and specification. [Note : A power point from junction is of average 8 rm per point]	pts.	16.00			
3.39	Supply and installation of 13A/ 16 A single phase 3 pin socket point wiring for City supply and Generator /UPS (computer supply) with 2 x 4 sq mm+1x 1.5 sq mm pvc insulated multi stranded copper wires through 20 mm internal dia Hard cover conduit concealed from DB to various points through pool boxes wherever required no junction boxes shall be used (both City with round pin socket and generator back up points with flat pin sockets) as per drawing and specification. [Note : A power point along with its switch and juction shall be counted as a pointand the average rm per point is 12 rm from DB to point]	pts.	92.00			

Electrical wiring and fitting work
CPV: 45311000-0 - Electrical wiring and fitting work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
3.40	Supply & Delivery of Sockets (MAKE : Clipsal/ Orange or eqvt) 5 A, 2 pin sockets	nos	16.00			
3.41	15 A, 3/5 pin Round pin power socket with control switch and indicator light .	nos.	92.00			
3.42	Supply and installation of fan point wiring with with 2 x 4 sq mm +1x1.5 sq mm pvc insulated multi stranded copper wires through 20 mm internal dia MS conduit along with MS Box, concealed from SDB to various fan points as per drawing and specification.	pts.	20.00			
3.43	8/10" dia Heavy duty metal body exhaust fan with complete canopy work	set	4.00			
3.44	48" dia ceilling fan with complete installation materials	set	12.00			
3.45	Supply and installation of earth electrode made of 60cm x 60 cm x 3 mm copper plate including 25 x 3 mm cu strip connection up to earth test bench with all required materials for earthing as per drawing and specification.	set	4.00			
3.46	Supply, Installation & commissioning of following - 25 mm x 3 mm cu-strip for Lightening arrester down conductor in exterior bolted in 25 mm size rectangular bush fixed in exterior wall in 700 mm spacing	m	18.00			
3.47	Supply, Installation & commissioning of following - Arrester made of pure Cupper	set	1.00			
3.48	Supply and installation of TV point wiring from Television Block Spliter to individual point with coaxial cable through 20 mm dia PVC conduit concealed including GI 3"x3" (epoxy quoted) metal box concealed as per drawing and specification.[Note : average length considered is 15 rm from the Splitter DP]	pts	24.00			
3.49	Supply and installation of TV socket in concealed metal as per drawing and specification.	nos	24.00			

Electrical wiring and fitting work CPV: 45311000-0 - Electrical wiring and fitting work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.50	Supply and installation of following TV Splitters concealed as per drawing and specification; Floor Splitter box (flush type) 1 :4 splitter with amplifier base and Second floor	nos	3.00			
3.51	Back bone cable (optical fibre or no loss cu coaxial cable) from the main connection to Main splitter and Floor splitter.	m	28.00			

Total Item Price	
VAT (13.00%)	
Grand Total	