Bill of Quantities (BOQ)

Upgrading of Paanch Kilo Toribaari Chhap Saatdobato Sadak Go.Na.Pa-13,Gorkha.

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/28/083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[GCC19]	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
PS.2	Relocation of Services and repairing for existing infrastructure (houses, water supply pipes, HDPE pipes, Electric Poles, Temple, Foot staircase, Foot trail etc) for social and environmental compliance as instructed by engineer's. [SSRBW Clause 105]	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Road Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			
1.2	Road way Excavation in all types of soil, Ordinary Rock & hard Rock(using Breaker) as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. [SSRBW 905.]	Cum	227.40			
1.3	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	4.00			

Road Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	90.60			
1.5	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork)[SSRBW: 2000]	Cum	27.80			
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork)[SSRBW: 2000]	Cum	75.00			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications [SSRBW: 2014]	KG	3,151.23			

Total Item Price	
VAT (13.00%)	
Grand Total	