Bill of Quantities (BOQ)

Chhaldi Panaha Palukha Motarbato Staronnati

IFB No.: 801055203/OIRM/GUL/NCB/WORKS/083/84-18

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property as per specified in Contract Document and scale of the project as per GCC.	PS	1.00	13,000.00 Thirteen thousand rupees only.	13,000.00 Thirteen thousand rupees only.
PS.2	Providing and Installation of project signboards with size of 1.8x1.2 m as per specification and instruction of engineer.{110}	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Carryout laboratory test for material and works as requied and Relocation of services/minor infrastructures, as per Engineer's instructions.	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				33,000.00 Thirty-three thousand rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation, Drain Cutting in all types of Soil/Rock by mechanical means including removal of stumps and other deleterious matter, all lifts and lead as per Drawing, Specifiction and instruction of the Engineer. [SS/SP- 905]	Cum	115.80			
1.2	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil	Sqm	810.60			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and Laying Plum Concrete (60% M15 Concrete and 40% boulders/stones) with proper weephole including formwork, scaffolding, other necessary accessories, Curing etc all complete as per Drawing and Specification. [SS/SP- 2421]	Cum	24.34			
1.4	Providing and laying, fitting and placing HYSD bar reinforcement complete as per drawing and technical specifications. [SS/SP- 2014]	M.T.	5.64			
1.5	Providing and laying of PCC/RCC M20 including necessary formwork and other accessories, curing etc. all complete as per Drawing and Technical Specifications.(Soling Existing) [SS/SP- 2000]	Cum	121.59			

Total Item Price	
VAT (13.00%)	
Grand Total	