Bill of Quantities (BOQ)

Construction and Maintenance of Avi, Football Maidan, Surya, Uday Path

IFB No.: 801054801/09/BSMC/IDD/WORKS/NCB-083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply and placing project information board/ hoarding boards, carryout necessary lab test and photography of work, event and materials as per requirement and instruction, all complete	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Insurance for the loss or damage to works, plants, materials, equipment, property and personal injury or death including Employer, Contractor and third parties as per conditions of contract.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	Provisional Sum for any relevant unforeseen work items as necessitated and instructed by an engineer.	PS	1.00	32,000.00 Thirty-two thousand rupees only.	32,000.00 Thirty-two thousand rupees only.
	Total provisional sums				1,02,000.00 One lakh two thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Compacting layer below existing wearing course after loosening material upto a level of 500 mm below, watered, graded and compacted in layers	sqm.	1,755.31			
1.2	Providing and laying granular subbase on prepared surface, mixing at OMC, and compacting to achieve the desired density and all complete	cum.	33.76			
1.3	Crusher Run Macadam Base. Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer as per Technical Specifications.	cum.	167.42			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and applying prime coat with hot bitumen MC 30/70 (including cutter)on prepared surface of granular base including cleaning of road surface and spraying as per Technical specification.	sqm.	2,092.87			
1.5	Providing and applying tack coat with hot Bitumen at the specified rate on prepared surfaces including cleaning as per Technical Speciation .	sqm.	2,092.87			
1.6	Providing and laying Asphalt concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Technical Specifications	cum.	73.919			

Total Item Price	
VAT (13.00%)	
Grand Total	