Bill of Quantities (BOQ)

Chisodhara Dekhi Piecs Laysis Hudai Batitole Pandheri Dhara Jane Road, Kakani RM 1, Nuwakot

IFB No.: IDONUWAKOT/W/NCB/10/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Provide and maintain traffic safety, Occupation Health and Safety (OHS) as per special provision,control measures and temporary diversions during construction as instructed by the Engineer.(DoR SS 104)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				70,000.00 Seventy thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works.(DoR SS 110)	No	1.00			
1.2	Earthwork in excavation of Foundation of structures for all types of soil , including construction of shorring and bracing, removal of stumps and other deleterious matter and backfilling with aproved materials as per drawing and technical specification.(DoR SS 907)	Cum	331.20			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Roadway excavation in all types of soil & Rock as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	Cum	776.25			
1.4	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications.(DoR SS 1201)	Cum	163.01			
1.5	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(DoR SS 1006)	Cum	31.05			
1.6	Providing and laying of Plain/Reinforced Cement Concrete M20 (1:1.5:3) Including Formworks in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	207.00			
1.7	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification(DoR SS 2014)	MT	6.52			
1.8	Providing and laying of Plain Cement Concrete M15 (1:2:4) in Foundation complete as per Drawing and Technical Specifications.(DoR SS 2000)	Cum	20.70			
1.9	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones Including Formworks .(DoR SS 2421) Using Mechanical Means	Cum	62.10			

Total Item Price	
VAT (13.00%)	
Grand Total	