Bill of Quantities (BOQ)

Upgradation of Bangai Danda to Mini Phewa Taal Road & Purwa Mainahiya -Saat kulo Butwal Road ,ward 2 &3

IFB No.: 50806/NCB/SRM/11/083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provision for Lab test according to standard specfication, Unforessen works & Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.	PS	1.00	45,000.00 Forty-five thousand rupees only.	45,000.00 Forty-five thousand rupees only.
	Total provisional sums				45,000.00 Forty-five thousand rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Supply and fitting of 3'x4' Information board, Diversion Boards, including letter as per instruction of site engineer.	No	2.00			
1.2	Scarifying the existing bituminous road surface to a depth of 50 mm and disposal of scarified Material with in all lifts and lead as per Drawing and Technical Specifications.	Sqm	704.55			
1.3	Crusher Run Macadam Base. Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications. By Mix in palce method. ii) for 45mm maximum size	Cum	181.13			
1.4	Providing and applying prime coat with hot bitumen MC 30/70 (including cutter)on prepared surface of granular base including cleaning of road surface and spraying at specified rate by mechanical means as per Technical specification.	Sqm	1,786.50			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and applying tack coat with hot Bitumen By Mechanical Means at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation .	Sqm	1,725.53			
1.6	Providing and laying Bituminous concrete/ Asphalt concrete (grade II) using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Drawing and Technical Specifications	Cum	67.06			

Total Item Price	
VAT (13.00%)	
Grand Total	