Bill of Quantities (BOQ)

Bara kalaiya U.Ma.Na.Pa. Waḍa No. 8 Barewa sannjaya sahako ghara dekhi paschima jane saḍaka ko sttaronnati

IFB No.: 3370121012/IDOBARA/NCB/W/02/2083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss of damage to works, plant, material, equipment, property and personnel injury or death including third party Insurance as per condition of contract.(SS/SP-100).	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
PS.2	Carryout additional tests for material and works as per required and instructed by the Project Manager.	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.3	Providing and installation of project signboards with size of 0.9 x 1.2 m in place including steel tube, painting, writing and supporting steel angle nut and bolt etc as per specification and instruction of engineer. (SS-110)	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				77,000.00 Seventy-seven thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Site Clearance:Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness (By Mechanical Means)-In area of Light Junglee (less than 15 number per 100 sqm)(SS-201)	Sqm	1,600.00			
1.2	Excavation as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction of the Engineer. (SS/SP - 905)	Cum	144.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(SS-2106)	Cum	55.00			
1.4	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for nominal mix) in Foundation complete as per Drawing and Technical Specifications.(SS-2000)	Cum	33.00			
1.5	Providing and laying of Plain Cement Concrete M 20 (or 1:1.5:3 for nominal mix) for drain by using crushed aggregate inclunding formworks, vibrator etc. complete as per Drawing and Technical Specifications.(SS-2000)	Cum	222.00			
1.6	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in Superstructure as per drawing and technical specification and Engineers instructions all complete.(SS-2014)	Kg	11,571.80			
1.7	Providing, laying, spreading and compacting embankment with roadway cutting material and compact to the required density as per Drawing and Technical Specifications. (SS-909,910)	Cum	120.00			

Total Item Price	
VAT (13.00%)	
Grand Total	