Bill of Quantities (BOQ)

Bankasiya Kushmaa Sadak Starbriddhi Kapilvastu Na. Pa. 9

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/28

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment) [1003,1005]	Sqm	745.65			
1.3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.(1201)	Cum	111.85			
1.4	Providing and laying of at least 125 micron thick polyethylene sheet on the prepared surface of base/subbase before laying Ready Mix Concrete (RMC) as per the direction of the engineer.	Sqm	662.80			
1.5	Providing and laying of Ready mix Concrete (RMC) of Grade M 20/20 for rigid pavement all completes as per Drawing and Technical Specifications	Cum	99.42			
1.6	Providing, preparing and installing form work including necessary supports and removing after completion for walls, foundation & structures[1804.1805]	Sqm	49.71			
1.7	Supply & place naturally found or quarry sieved loose gravel material including levelling all completes as per Specifications.[1201]	Cum	12.43			

Total Item Price	
VAT (13.00%)	
Grand Total	