Bill of Quantities (BOQ)

Upgrading Works of Nayabajar Thumke Jaubari Tumling Megma Tourism Road

IFB No.: 801010307/MJRM/NCB/WORKS /083/084-01

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the damage and loss of works,plants,and vehicles;personal injuries,death of labours,Employees and other third party Insurance	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
PS.2	Construction materials test as directed by site Engineer	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	1500 x 1200 mm Size Site information board as specified	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Works for complete or part construction and civil engineering work CPV: 45200000-9 - Works for complete or part construction and civil engineering work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (MECHANICAL MEANS)	cum	1,162.90			
1.2	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical	cum	57.00			
1.3	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete	cum	690.20			

Works for complete or part construction and civil engineering work CPV: 45200000-9 - Works for complete or part construction and civil engineering work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Dry Stone Masonry Work as per Drawing and Technical Specifications.	cum	8.25			
1.5	Providing and laying granular sub-base on prepared surface, without compaction all complete as per Drawing and Technical Specifications.	cum	62.00			

Total Item Price	
VAT (13.00%)	
Grand Total	