Bill of Quantities (BOQ)

Siraha Sukhipur Na.Pa. 7 Shiv Chowk Dilip Mahatoko Ghar Dekhi Ashok Rukh Samma RCC Dhalan

IFB No.: 3370116012/10-083/84/IDO/Siraha

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as described on Condition of Contract	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Carry out additional test for material and works per required and instructed by the Project Manager	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.3	Reallocation of services and minor infrastructure as per specification and as instructed by the Project manager (electrick pole)	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				75,000.00 Seventy-five thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Project sign board	No	1.00			
1.2	Formation of embankment including excavation, transportation, filling, compaction in layers and watering all complete. (Spec. cl-909)	Cum	232.00			
1.3	Preparation of subgrade by grading, watering & compaction in all types of soil and rocks for upgrading of the road as directed by the engineer all complete. (SS/SP 1000)	Sqm	1,200.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing, laying spreading, watering leveling and compaction of sieved gravel sub base grading as per table 12.1 of standard specification including transportation from the source as directed by the Engineer all complete (SS/SP 1201)	Cum	120.00			
1.5	Providing, laying spreading, watering leveling and compaction of wet mixed crushed stone base course material grading as per standard specification including transportation from the source as directed by the Engineer.-(SS/SP -1204)	Cum	120.00			
1.6	Providing and Placing machine(weight batching) mixed cement concrete M20/20 including compaction, curing, testing, formwork, Casting, curing, finishing all complete as per engineer's instruction.all complete for safety barrier. (SS/SP-2000)	Cum	240.00			
1.7	Providing and laying reinforcement including cutting, bending,binding,fixing in position etc.all complete. (SS/SP-2600)	MT	7.39			

Total Item Price	
VAT (13.00%)	
Grand Total	