Bill of Quantities (BOQ)

Upgrading Works of 1 no ward office Road

IFB No.: 801010307/MJRM/NCB/WORKS /2083/84-06

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the damage and loss of works,plants,and vehicles;personal injuries,death of labours,Employees and other third party Insurance	PS	1.00	18,000.00 Eighteen thousand rupees only.	18,000.00 Eighteen thousand rupees only.
PS.2	Construction materials test as directed by site Engineer	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	1500 x 1200 mm Size Site information board as specified	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				40,000.00 Forty thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (MECHANICAL MEANS)	cum	266.60			
1.2	Stone pitching/ Soling work on the prepared bedding with filling of voids by granular material/ spalls as per direction of the engineer all complete	cum	48.20			
1.3	"Providing, Preparing and Installing form work including necessary supports and removing after completion for precast element/ all type of structures. Class F3 Finish I) Square/ Rectangular/ Circular Sections/ Verticle surfaces a) Using Timber & Plywood"	sqm	146.85			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying, fitting and placing HYSD/ Mild Steel bar reinforcement in sub-structure complete as per Drawing and Technical Specifications	kg	1,056.44			
1.5	Providing and laying of Plain/ Reinforced Cement Concrete (RCC Grade M20) in Foundation complete as per Drawing and Technical Specifications.	cum	34.86			
1.6	"Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications A. 60% M 15 concrete and 40% boulders/ stones (Using Mechanical Aids)"	cum	18.48			
1.7	Precast interlocking blocks of 60mm th. on the prepared floor (bed preparation by sand & compaction if necessary) over stone dust/ local quarry sand at joints (min 10% colour)	sqm	140.00			

Total Item Price	
VAT (13.00%)	
Grand Total	