Bill of Quantities (BOQ)

Upgrading of Dhananjaya Marga, Bhanu-04, Tanahun (Sewa Bagaicha Dekhi Bhanu Janmasthal Marga Jodne)

IFB No.: 3370138034/IDO/TANAHUN/NCB/W/08/083-084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document [GCC 19]	PS	1.00	22,000.00 Twenty-two thousand rupees only.	22,000.00 Twenty-two thousand rupees only.
	Total provisional sums				22,000.00 Twenty-two thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer. [SSRBW Clause 110]	Nos.	1.00			
1.2	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [SSRBW Clause 907]	Cum	142.12			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.. [SSRBW Cause 3111]	Cum	42.75			
1.4	Providing and laying of Plain/Reinforced Cement Concrete M15 in foundation complete as per drawing and technical specifications (including Forms works). (SSRBW Cause 2000)	Cum	21.37			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying stone masonry work in cement mortar 1:4 in structure complete as Including Weephole and backfilling per drawing and technical specifications (Random Rubble Masonry) . (SSRBW Clause 2602,2603 2607)	Cum	123.85			
1.6	Providing and laying Plumb Concrete (Boulder Mixed Concrete) including weephole and backfilling as per Drawing and Specifications 60% M15 concrete and 40% boulders/stone using Mechanical Means (including formwork).(SSRBW Cause 2421)	Cum	51.60			
1.7	Providing and laying of Reinforced Cement Concrete in Superstructure complete as per Drawing and Technical Specifications. Grade M20(Including Formwork) (SSRBW Cause 2000)	Cum	1.65			
1.8	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications. [SSRBW-2014]	Kg	255.46			

Total Item Price	
VAT (13.00%)	
Grand Total	