Bill of Quantities (BOQ)

Upgrading Of Radio Nepal Purwa Sadak, Birendranagar-01, Surkhet

IFB No.: 3370168016/02-IDO/SKT/W/NCB/16/083-084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's and Consultants's staff personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract.	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.00	19,000.00 Nineteen thousand rupees only.	19,000.00 Nineteen thousand rupees only.
	Total provisional sums				69,000.00 Sixty-nine thousand rupees only.

General Item

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.2 m X 0.9 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.	Nos.	1.00			

Drain Construction Works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
2.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications.	Cum	294.25			

Drain Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	108.90			
2.3	Providing and laying of Plain/Reinforced Cement Concrete in structures complete including formwork as per Drawing and Technical Specifications, PCC Grade M 15.	Cum	271.92			
2.4	Providing and laying of Plain/Reinforced Cement Concrete in structures complete including formwork as per Drawing and Technical Specifications, PCC Grade M 20.	Cum	3.75			
2.5	Providing and laying , fitting and placing Mild steel / HYSD reinforcement complete in sub-structure/super-strucure as per drawing and technical specification.	MT	0.36			

Pavement Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
3.1	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications	Cum	693.00			

Total Item Price	
VAT (13.00%)	
Grand Total	