Bill of Quantities (BOQ)

Durga Sanskrit Ved Vedangga Vidyapithko Adhuro Bhawan Nirman, Tilottama-14, Durganagar, Rupandehi

IFB No.: 3500048075/SDDO/NCB-06/083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Installation of Project Signboard of proper dimensions, complete as directed by the Engineer.	No.	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
PS.2	Additional Quality Control Tests beyond routine tests and other Unforeseen Works, when considered necessary by the Engineer.	PS	1.00	4,490.13 Four thousand four hundred ninety rupees and thirteen paisa only.	4,490.13 Four thousand four hundred ninety rupees and thirteen paisa only.
PS.3	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				32,490.13 Thirty-two thousand four hundred ninety rupees and thirteen paisa only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing, laying, compacting and curing M25 (1:1:2) plain cement concrete for column, slab, beams, tie beam and all kinds of R.C.C. works with cement sand and stone ballast 20mm down finishing to approved level, line and dimensions (including addition of PVC/HDPE pipes for Electrical Conduits with necessary electrical boxes and sockets) all complete as per specifications, drawings and instructions of the site engineer, all complete.	cum	83.09			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Providing,Supplying laying & Centering and shuttering with plywood for Column, Beam, Slab & other RCC work including all necessary propping, scaffolding, staging, supporting, dismantling and clearing from the site, including shuttering all complete as per design drawings, specifications and instruction of the site engineer .	sqm	561.67			
1.3	Providing,Supplying ,Cutting and laying Reinforcement bars (Grade Fe500) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation, column, beam, wall, staircase, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	kg	11,269.57			
1.4	Providing, laying and curing first class brick masonry works for Sub-Structures/super Str in cement, sand mortar (1:6) in perfect lines & level as per specification, drawings & instructions of the site engineer.	cum	4.42			

Total Item Price	
VAT (13.00%)	
Grand Total	