Bill of Quantities (BOQ)

Slab Culvert and Cross Drainage Works along Lamidanda-Simbhanjyang-Palung-Tistung-Sopyarg (DB) Section of TRP (NH41), Makwanpur

IFB No.: 337013201/08/RDHTD/33701132/2083/084-32

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

Construction work #[45000000] Road construction works **CPV: 45233120-6 - Road construction works**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Insurance for loss of or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data including mobilization, demobilization expenses for manpower, equipment and performance bond commision. (GCC Clause no 13)	LS	1.00			
2.2	Traffic flow management either by diversion or controlled access with the help of traffic police and /or trained personnel; by providing traffic safety and personnel safety,assurance by announcements through public media etc	LS	1.00			
2.3	Dismantling of existing structures like culverts, bridges, retaining walls and other structure comprising of masonry, cement concrete, wood work, steel work, gabion work, including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead of 1000 meters. (SS 202)	LS	1.00			

Construction work #[45000000] Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.4	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means) (SS 907)	Cu.m.	186.52			
2.5	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (SS 1000)	Cu.m.	38.10			
2.6	Providing and laying of PCC (Grade M 15) in foundation complete as per Drawing and Technical Specifications (SS 2000)	Cu.m.	18.58			
2.7	Providing and laying of RCC (Grade M 30) in foundation complete as per Drawing and Technical Specifications. (SS 2000)	Cu.m.	57.01			
2.8	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	M.T.	2.22			
2.9	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc including form works all complete as per Drawing and Technical Specifications. (Mechanical Means) (SS Clause 2421)	Cu.m.	69.13			

Total Item Price	
VAT (13.00%)	
Grand Total	