Bill of Quantities (BOQ)

Dhampur mul sadakko paschim patti lakshiramko ghardekhi dak budhako ghar samma pakki nali nirman

IFB No.: 801055804/BMO/NCB/W/2083-84/1

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply, deliver, and install a standard-size project information board as per approved specifications. Provide and maintain all required insurances for the project duration, including Insurance of Works, Equipment, Contractor's Workmen/Employees, and Third-Party Liability against damage to persons and property. Carry out additional tests for materials and works as required and instructed by the Engineer. Provide a Provisional Sum for the operational and logistical expenses of the project management team (Project Manager, Site In-charge, Site Supervisor, and Monitoring Committee). This sum strictly covers actual fuel and oil for site visits, vehicle maintenance, and miscellaneous administrative or meeting expenses. It shall be expended or deleted at the sole discretion of the Engineer. Reimbursement will be made on a remeasurement basis against genuine tax invoices and logbooks, with zero contractor profit or markup allowed."	PS	1.00	50,658.12 Fifty thousand six hundred fifty-eight rupees and twelve paisa only.	50,658.12 Fifty thousand six hundred fifty-eight rupees and twelve paisa only.
	Total provisional sums				50,658.12 Fifty thousand six hundred fifty-eight rupees and twelve paisa only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm	327.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum	228.90			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum	49.05			
1.4	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications	cum	24.53			
1.5	Providing and laying of RCC (Grade M 20) in foundation including formwork complete as per Drawing and Technical Specifications	cum	129.33			
1.6	Providing and laying, fitting and placing HYSD bar reinforcement in foundation complete as per Drawing and Technical Specifications (SS Clause 2014)	kg	11,641.47			
1.7	Providing, laying, embankment with transported material(soil) in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)	cum	81.75			

Total Item Price	
VAT (13.00%)	
Grand Total	