Bill of Quantities (BOQ)

Chhatrekhola Sadak Pul, Tarkeshwor Rural Mun 4 & Bidur Mun 3, Nuwakot

IFB No.: IDONUWAKOT/W/NCB/4/2083-84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.2	Provide and maintain traffic safety, Occupation Health and Safety (OHS) as per special provision,control measures and temporary diversions during construction as instructed by the Engineer.(DoR SS 104)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				60,000.00 Sixty thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfilling etc all complete as per DoR Standard Specification for Road and Bridge Works.(DoR SS 110)	No	1.00			
1.2	Earthwork in excavation of Foundation of structures for all types of soil , including construction of shorring and bracing, removal of stumps and other deleterious matter and backfilling with aproved materials as per drawing and technical specification.(DoR SS 907)	Cum	345.25			
1.3	Providing Suitable material and backfilling Locally available Material including compaction by tamping rod as per Drawing and Technical Specifications(DOR SS 908)	Cum	61.08			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones Including Form works .(DoR SS 2421) Using Mechanical Means	Cum	144.00			
1.5	Providing and laying mechanically woven double twisted crates / mattress consisting of Heavy zinc coated Hexagonal mesh type 100 mm x 120 mm, mesh wire 3 mm, selvage wire 3.9 mm, lacing wire 2.4 mm Gabion structure for retaining earth with diaphragm including rolling, cutting , assembling , placing,laying sides and diaphragms with binding wire and filling boulders all complete as per Drawing and Technical Specification. (DoR SS 2402)	Cum	510.50			
1.6	Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.(DoR SS 2404)	Sqm	317.00			

Total Item Price	
VAT (13.00%)	
Grand Total	