Bill of Quantities (BOQ)

Recurrent Maintenance Works along Hetauda-Sarashwati Khola-Lothar Section of MRM (NH01), Makwanpur

IFB No.: 337013201/08/RDHTD/337310113/2083/084-31

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

Construction work #[45000000] Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Insurance for loss of or damage to works, plant, material, equipment, property and personnel injury or death and third party as per contract data including mobilization, demobilization expenses for manpower, equipment and performance bond commision. (GCC Clause no 13)	LS	1.00			
2.2	Providing and laying 50 mm thick penetration macadam over prepared base by providing a layer of compacted crushed coarse aggregate with application of bituminous binder and key aggregates as per Drawing and Technical Specifications [1304]	Sq.m.	1,181.46			
2.3	Providing and Supplying Tack coat with hot paving grade VG 10 bitumen by mechanical means at specified rate on the prepared surface including cleaning as per the Technical Specification. [1302]	Ltr	5,696.72			
2.4	Providing and laying close-graded premix surfacing material of 20 mm thickness composed of 11.2 mm to 0.09 mm or 13.2 mm to 0.09 mm aggregates using bitumen as wearing course on a previously prepared base, including mixing in a suitable plant as per Drawing and Technical Specifications. [1310]	Sq.m.	14,241.80			

Total Item Price	
VAT (13.00%)	
Grand Total	