Bill of Quantities (BOQ)

Upgrading Of Namjung Barchula Rambhanjyan Bunkotghat Road, Sahidlakhan RM-09,Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/19/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipment, contractor's workmen and employees and third party insurance against damage to other persons and property as per specifications and instructions of the engineer (GCC 19)	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				30,000.00 Thirty thousand rupees only.

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer	no.	1.00			
1.2	Earthwork in excavation of foundation of structures in all types of soil an rock by mechanical means, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved material, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 900, 907)	Cum	51.75			
1.3	Providing and laying of hand packed stone soling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawings, technical specifications and instructions of the engineer (SSRBW 1000, 3111)	Cum	112.55			
1.4	Providing and laying of M15 PCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	Cum	14.40			

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying of stone masonry work in machine-mixed 1:4 cement sand mortar including providing weep holes, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2600, 2602, 2603, 2607, 3109)	Cum	12.00			
1.6	Providing and laying of M20 concrete for RCC including formworks, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000)	Cum	102.20			
1.7	Providing and laying, fitting and placing HYSD reinforcement, all complete as per drawings, technical specifications and instructions of the engineer (SSRBW 2000, 2014)	KG	4,181.28			

Total Item Price	
VAT (13.00%)	
Grand Total	