Bill of Quantities (BOQ)

Settlement Development Program Juthapauwa Bazar Conservation and Juthapauwa Parking, Rainadevi Chhahara-6, Palpa

IFB No.: 3470150015/UDBOP-NCB-083/84-12

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	24,000.00 Twenty-four thousand rupees only.	24,000.00 Twenty-four thousand rupees only.
PS.2	Material Tests	PS	1.00	14,916.00 Fourteen thousand nine hundred sixteen rupees only.	14,916.00 Fourteen thousand nine hundred sixteen rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
	Total provisional sums				40,916.00 Forty thousand nine hundred sixteen rupees only.

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Dismantling of existing masonary / concrete structures like Road , drain side walls and including scaffolding wherever necessary, sorting the dismantled Material, disposal of unserviceable Material and stacking the serviceable Material with all lifts and lead (by Mechanical Means).	cum.	26.94			
1.2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	202.96			

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum.	98.88			
1.4	Reusing of Dismantled Stone masonry work in soling&wall work all material and labour complete as per instruction , specification and drawing.	Cum	5.83			
1.5	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	67.85			
1.6	Providing and laying of PCC 1:2:4 (Grade M 15) in foundation complete as per Drawing and Technical Specifications	cum.	16.19			
1.7	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% Boulders/stones Mechanically with formwork (water proof ply wood or equivalent material).	cum.	29.30			
1.8	Providing and laying Reinforcement Cement Concrete RCC(GradeM20)Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	46.43			
1.9	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	Kg	1,545.63			
1.10	Construction of stone masonry for Retaining walls/drains in 1:4 cement-sand mortar with 4" HDPE pipe weep hole including supply of materials, curing all complete.	cum.	59.18			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.11	Providing and Pointing with cement mortar (1:3) on masonry work in structure as per Technical Specifications	Sqm	59.60			
1.12	Providing and supplying fabricating,welding,erecting and fixing MS Black Steel Square section of specified size and thickness including cutting drilling welding ,grinding one coat of anti -corrosive primer necessary fitting and all incidental works complete as per approved drawing technical Specifications and instructions of the Engineer	Kg	288.00			

Total Item Price	
VAT (13.00%)	
Grand Total	