Bill of Quantities (BOQ)

Karkitol Mangala Ma.Vi. Hudai Thapatol sadak Staronnati Panchakannya-4, Nuwakot

IFB No.: IDONUWAKOT/W/NCB/8/2083-84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property(GCC 13)	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
PS.2	Provide and maintain traffic safety, Occupation Health and Safety (OHS) as per special provision,control measures and temporary diversions during construction as instructed by the Engineer.(DoR SS 104)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.3	Carry out additional tests for material and works as required and instructed by the Project Manager.(GCC 33.1)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.(DoR SS 110)	No.	1.00			
1.2	Roadway excavation in all types of soil as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer. (DoR SS 905)	m3	984.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Earthwork in excavation of Foundation of structures, including construction of shorring and bracing, removal of stumps and other deleterious matter and backfilling with aproved materials as per drawing and technical specification.(DoR SS 907)	m3	170.00			
1.4	"Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.(DoR SS 1006) "	m3	146.63			
1.5	Providing and laying of Plain Cement Concrete M15 complete as per Drawing and Technical Specifications.(DoR SS 2000)	m3	7.65			
1.6	Providing and laying of Reinforced Cement Concrete M20 complete as per Drawing and Technical Specifications.(DoR SS 2000)	m3	170.00			
1.7	Providing and laying , fitting and placing HYSD/TMT bar reinforcement complete as per drawing and technical specification(DoR SS 2014)	MT	4.146			
1.8	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% boulders/stones(Including weepholes and formworks) .(DoR SS 2421)	m3	11.90			

Total Item Price	
VAT (13.00%)	
Grand Total	