Bill of Quantities (BOQ)

Nagawa Gau dekhi Gadulganga Vidhyalaya hudai Gau Chok samma ko Sadak Staronnati, Kapilvastu 10

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/30

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment) [1003,1005]	Sqm	579.65			
1.3	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.(1201)	Cum	69.56			
1.4	Providing and laying of at least 125 micron thick polyethylene sheet on the prepared surface of base/subbase before laying Ready Mix Concrete (RMC) as per the direction of the engineer.	Sqm	521.69			
1.5	Providing and laying of Ready mix Concrete (RMC) of Grade M 20/20 for rigid pavement all completes as per Drawing and Technical Specifications	Cum	78.25			
1.6	Providing, preparing and installing form work including necessary supports and removing after completion for walls, foundation & structures[1804.1805]	Sqm	34.78			
1.7	Supply & place naturally found or quarry sieved loose gravel material including levelling all completes as per Specifications.[1201]	Cum	6.96			

Total Item Price	
VAT (13.00%)	
Grand Total	