Bill of Quantities (BOQ)

Upgrading Of Phishling Aaedanda Banatar Phishling Jodne Ring Road Gandaki R.M-06, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/17/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[GCC19]	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
PS.2	Reallocation of services and minor infrastructures and Environment Protection Work as per specification and as instructed by the Project Manager.[SP/SS-111]	PS	1.00	35,000.00 Thirty-five thousand rupees only.	35,000.00 Thirty-five thousand rupees only.
	Total provisional sums				85,000.00 Eighty-five thousand rupees only.

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SSRBW 110]	Nos	1.00			
1.2	Road way Excavation in all types of soil and rock as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer.[SSRBW-907]	Cum	600.00			
1.3	Earth work in excavation of foundation of structures, including soil and rock, construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [SSRBW-907]	Cum	644.73			
1.4	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SSRBW 2602,2603,2607].	Cum	170.35			

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SSRBW 1006].	Cum	129.35			
1.6	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) [SSRBW: 2000]	Cum	176.48			
1.7	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork) [SSRBW: 2000]	Cum	4.80			
1.8	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications [SSRBW: 2014]	KG	187.65			

Total Item Price	
VAT (13.00%)	
Grand Total	