Bill of Quantities (BOQ)

Construction of Building: Jana Jiven aa vi Gaumukhi Ga pa-04,Pyuthan

IFB No.: 3500055015/03-SDDO/NCB-083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Hoarding Board	PS	1.00	2,000.00 Two thousand rupees only.	2,000.00 Two thousand rupees only.
PS.2	lab test of materials	PS	1.00	11,775.50 Eleven thousand seven hundred seventy-five rupees and fifty paisa only.	11,775.50 Eleven thousand seven hundred seventy-five rupees and fifty paisa only.
PS.3	Insurance	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
	Total provisional sums				38,775.50 Thirty-eight thousand seven hundred seventy-five rupees and fifty paisa only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	E/W excavation in earth work for all type of soils by mechanically	cum	68.82			
1.2	E/W excavation in earth work for hard type of soils by mechanically	cum	17.20			
1.3	Back filling work	cum	43.01			
1.4	Dry stone soling in foundation and floor including sand filling in joints, levelling, watering etc. all complete.	cum	6.9941			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Plain cement Concrete (PCC) in 1:3:6 ratio for foundations, flooring and walls with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	cum	3.50			
1.6	Rubble masonry work in inclined level in 1:6 C/S mortar in perfect line level finish including, racking the joints and curing the work for at least 7 days all complete.	cum	17.00			
1.7	Plain cement Concrete (PCC) for RCC works (1:1.5:3) for slab/lintels with approved quality of cement and sand and crushed stone aggregate including mixing, laying, curing etc all complete in approval of site engineer.	cum	45.69			
1.8	Formwork, shuttering, centering with approved materials for all works necessary propping, scaffolding, staging, supporting inclusive of wedging and cutting holes for utilization till the support if fully unyielding nett.	sqm	295.92			
1.9	Tor steel reinforcement bar of fe 415/500 grade including straightening, cleaning, cutting, binding & fixing in position with annealed tying binding wire as per drawing, design & instruction all complete.	kg	5,186.45			

Total Item Price	
VAT (13.00%)	
Grand Total	