Bill of Quantities (BOQ)

Sunwal Nagarpalika ward no:03 sthit aasambasi tol durga mandir purwa ghola tatbandhan nirman, Aasambasi durga mandir samrakshan, sunwal nagarpalika ward no 03 chandrajyoti aadharbhut bidhyalay uttar purwa nala nirman, chndrajyoti aadharbhut bidhyalay

IFB No.: 80547403/10.SUN/NCB/2083/84

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Lab Test Work including all necessary Test and providing Test Report all complete work as recommended by site engineer	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.3	Other Unseen Miscellenous Works (Dewatering work as well) as per approval. (Work Shall be done only on approval of the workorder by client as per approved norms and the payment of this item will be done according to submitted original copy ofrelated invoices)	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.4	Installation of Information board all complete work as recommended by site engineer	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				70,000.00 Seventy thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness.In Jungle By Machine .	SQM	307.54			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cubic meter	230.65			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones on prepared surface as per Drawing and Technical Specifications.	Cubic meter	41.51			
1.4	Providing and laying of PCC (Grade M 10) in foundation all complete with fair finish Formwork as per Drawing and Technical Specifications	Cubic meter	26.28			
1.5	Providing and laying Random Rubble Stone Masonry work in cement mortar 1:6 and providing necessary 100 mm dia HDPE pipes if required for weep holes etc all complete as per Drawing and Technical Specifications	Cubic meter	198.08			
1.6	Providing and Pointing with cement mortar 1:3 on masonry work in structure as per Technical Specifications	SQM	111.68			
1.7	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:4) on brickwork-stone masonary in structure as per Drawing and Technical Specifications	SQM	201.78			

Total Item Price	
VAT (13.00%)	
Grand Total	