Bill of Quantities (BOQ)

Construction of Lantibazar Lekpokhara Dahakhola Damachaur Kalakhet Road (43.81 km), Chhatreswori Municipality

IFB No.: 3370160016/02/IDO/SLN/W/NCB/02/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant, material, equipment property and personnel injury or death, including third party insurance . [GCC:19.1]	PS	1.00	42,500.00 Forty-two thousand five hundred rupees only.	42,500.00 Forty-two thousand five hundred rupees only.
PS.2	Providing and installation of Project Signboards with size of 1.8 x1.2m as per specification and instruction of Engineer. [SSRBW 110]	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				52,500.00 Fifty-two thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	373.20			
1.2	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per Drawing and Technical Specifications. [SSRBW 908]	Cum	149.82			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms)	Cum	11.57			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	"Providing and placing machine mixed cement concrete of M15/40 for the foundation and footing etc. including formwork, compaction,curing,testing etc all complete as per specification "	Cum	4.31			
1.5	Providing and laying of Plain Cement Concrete M10 in foundation complete as per Drawing and Technical Specifications.	Cum	4.36			
1.6	"Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including weep holes complete as per Drawing and Technical Specification. [SSRBW 2607 & 3109] "	Cum	164.86			
1.7	Providing and Assembling mechanically woven double twisted crates/mattress including rolling, cutting and with lacing wire and binding wire as per specification, Hexagonal mesh type 100mm * 120mm, mesh wire 3mm, selvage wire 3.9mm, lacing wire 2.4mm and Providing and filling stone/boulder in gabion boxes/mattress etc. Including dressing, bedding, bonding all complete as per Drwing and Technical Specifications. [SSRBW 2402]	Cum	367.50			
1.8	Providing , laying of geotextile filter as per Drawing and Technical Specifications.specification & instruction of Engineer [SSRBW 2404]	Sqm	220.00			
1.9	Providing and Laying RCC 900mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	17.50			

Total Item Price	
VAT (13.00%)	
Grand Total	