Bill of Quantities (BOQ)

Pashupatinath Mandir Purbadhar Nirman Sunwal 11

IFB No.: 80547403/12.SUN/NCB/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply and placing project information board/ hoarding boards as per requirement, all complete,	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
PS.2	Necessary lab test works for official purpose. (Regular reports for Quality Assurance of work done shall be under Contractor responsibility)	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
PS.3	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document	PS	1.00	15,000.00 Fifteen thousand rupees only.	15,000.00 Fifteen thousand rupees only.
	Total provisional sums				33,000.00 Thirty-three thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation Manually for foundation in Ordinary soil including necessary lead and lift.	cum	10.246			
1.2	Providing and Stone soiling in foundation and floor as per drawings, specification and instruction of the consultant/Engineer, all complete.	cum	4.91808			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:3:6 (1 cement : 3 sand : 6 coarse aggregate) for	cum	20.9238			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
	leveling course in foundations and floor of building, pathway, etc in all level with stone aggregate of size not more than 25 mm of approved quality dewatering, batching, mixing, transporting, placing, compacting with vibrator, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.					
1.4	Providing and laying machine mixed Plain Cement Concrete of nominal mix 1:1.5:3 (1 cement : 1.5 sand : 3 coarse aggregate) for leveling course in foundations and floor of building, pathway, etc in all level with stone aggregate of size not more than 25 mm of approved quality dewatering, batching, mixing, transporting, placing, compacting with vibrator, curing, including all lead and lift, etc. all complete as per drawings, specifications and the instructions of the Engineer.	cum	4.0984			
1.5	Providing and fixing in position Fe500 steel reinforcement of various diameter in R.C.C works including straightening, cutting, bending, binding with wire for tying the reinforcement bars at each junctions (binding wire shall not be measured separately) including all waste pieces, provision for adequate numbers of spacers, providing at all levels all complete as per drawings, specifications and instructions of the Engineer.	Kg	411.104938			
1.6	Supplying and laying centering, shuttering of various pattern formworks water proof ply wood & steel adjustable props for all kinds of RCC & PCC works for foundations, columns, shear walls, beams, slab, staircase, lintel, sill, pergola, including nails, propping scaffolding, staging, supporting and bracing in proper lines and level, sealing the joints,aligning to line and levels including Ties, PVC Spacer, Providing openings/ cutouts/ pockets,deshuttering as approved by the Engineer etc., complete at all levels as per drawing, specifications and instructions of the Engineer. FOR SLAB	sqm	163.936			
1.7	Supplying and erecting Grill works for Drain cover	KG	1,346.73424			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	Supplying & applying 2 coats Plastic Emulsion painting in Internal & External paint of approved colour with one coat of primer Painting over properly cleaned surface of building all complete as per approved drawing, Specification and instruction of site engineer.	sq.m	74.14			
1.9	Providing supplying and laying of 16mm thick granite work in 20mm thick (1:3) with pefect line and level with approved design and drawing (moulding,rubbing and polishing) as per drawing specification and instruction of site engineer all complete.	sq.m	177.7525			
1.10	Supplying and Laying of 25 mm thick flagstone with packing the joints with 1:4 cement sand motar as per specification and instruction of site engineer all complete.	sq.m	321.03415			

Total Item Price	
VAT (13.00%)	
Grand Total	