Bill of Quantities (BOQ)

Settlement Development work from Jamun Rukh to nursery Tansen-12 , Road Upgrading work at Neta Pokhara-Amdada-Abal Tansen-12 and Settlement Development Work at bauwagumba Magar Homestay, Tansen-13, Palpa

IFB No.: 3470150015/UDBOP-NCB-083/84-08

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	26,160.00 Twenty-six thousand one hundred sixty rupees only.	26,160.00 Twenty-six thousand one hundred sixty rupees only.
PS.2	Material Tests	PS	1.00	16,950.00 Sixteen thousand nine hundred fifty rupees only.	16,950.00 Sixteen thousand nine hundred fifty rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
	Total provisional sums				46,110.00 Forty-six thousand one hundred ten rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum.	362.94			
1.2	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	60.20			

Road construction works CPV: 45233120-6 - Road construction works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	99.64			
1.4	Providing and laying plain Cement Concrete PCC(Grade M15) Including batching , mixing, transporting,placing,,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	30.33			
1.5	Providing and laying Plum concrete (Boulder mixed concrete)including formwork as per Drawing and Specifications 60% M 15(1:2:4) concrete and 40% Boulders/stones Mechanically .	cum.	69.08			
1.6	Providing and laying Reinforcement Cement Concrete RCC(GradeM20) Including batching , mixing, transporting,placing, vibrating ,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	60.20			
1.7	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	kg	3,024.07			

Total Item Price	
VAT (13.00%)	
Grand Total	