Bill of Quantities (BOQ)

Upgrading Of Kantaar Namjungphat Jyaprang Manakamna Road Sahidlakhan R.M-03, Gorkha

IFB No.: 3370136014/IDO/GORKHA/NCB/W/R/18/083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.[SS DOR GCC19]	PS	1.00	50,000.00 Fifty thousand rupees only.	50,000.00 Fifty thousand rupees only.
	Total provisional sums				50,000.00 Fifty thousand rupees only.

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer[SS DOR 110]	Nos	1.00			
1.2	Earth work in excavation of foundation of structures in all types of soil and rock, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. [SS DOR-907]	Cum	420.65			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications[SS DOR 1006].	Cum	166.09			
1.4	Providing and laying of Machine mixed Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M15 (Including Formwork) [SSRBW: 2000]	Cum	41.64			
1.5	Providing and laying of Stone Masonry Work in Cement Mortar 1:4 in Foundation complete as per Drawing and Technical Specifications[SS DOR 2602,2603,2607].	Cum	51.22			

Construction work-Road Construction Work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Providing and laying of Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. Grade M20 (Including Formwork) [SSRBW: 2000]	Cum	136.01			
1.7	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications [SSRBW: 2014]	KG	5,568.49			
1.8	Supply of machine made hexagonal mesh type 100mm x 120 mm Gabion boxes / mattresses with diapharagms, with binding wire x swg, mesh wire 3mm and selvedged wire 3.9 mm and lacing wire 2.4 mm, including palcing in position including stretching, forming compartments; tying with bracing wires and tie wires; tying down the lid complete; and providing and filling stone / boulder in gabion boxes / mattresses etc. including dressing, beding, bonding and all transporation as per specification. [SSRW 2401,2402]	Cum	26.00			

Total Item Price	
VAT (13.00%)	
Grand Total	