Bill of Quantities (BOQ)

Ghuiyabari Swamibas Babai Road Kalimati Ga.Pa. 7 Salyan

IFB No.: 3370160016/02/IDO/SLN/W/NCB/09/2083/84

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant, material, equipment property and personnel injury or death, including third party insurance . [GCC:19.1]	PS	1.00	42,500.00 Forty-two thousand five hundred rupees only.	42,500.00 Forty-two thousand five hundred rupees only.
PS.2	Insurance for the loss of damage to works, plant, material, equipment property and personnel injury or death, including third party insurance . [GCC:19.1]	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				52,500.00 Fifty-two thousand five hundred rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	245.93			
1.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications. (Old Norms)	Cum	65.30			
1.3	"Providing and placing machine mixed cement concrete of M15/40 for the foundation and footing etc. including formwork, compaction,curing,testing etc all complete as per specification "	Cum	43.82			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	"Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes,Formwork etc all complete as per Drawing and Technical Specifications. (Mechanical Means) "	Cum	153.00			
1.5	"Providing and laying Random Rubble Stone Masonry work in cement mortar 1:4 in structure including pointing works and providing necessary 100 mm dia HDPE pipes for weep holes etc all complete as per Drawing and Technical Specifications "	Cum	54.10			
1.6	Providing and Laying RCC 900mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	22.50			
1.7	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm (0.0615 kg/m) & selvedge wire -3.9mm(0.1057kg/m) and Binding wire 12 SWG Box of different sizes as per requirements. (different size 1 m height Gabion box)	Cum	153.00			

Total Item Price	
VAT (13.00%)	
Grand Total	