Bill of Quantities (BOQ)

Mainahara Rajesh Chaudhary ko ghar dekhi Dakshin tarfa sadak Staronnati, Banganga Na. Pa. 11

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/23

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cium	115.50			
1.3	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cium	34.65			
1.4	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications	Cium	22.40			
1.5	Providing and laying of RCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications	Cium	60.35			
1.6	Providing and laying, fitting and placing HYSD bar reinforcement in super-structure complete as per Drawing and Technical Specifications	Ton	2.75			
1.7	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment)[1003,1005]	Sqm	724.50			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.8	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.[1201]	Cum	108.68			

Total Item Price	
VAT (13.00%)	
Grand Total	