Bill of Quantities (BOQ)

Barbardiya Nagarpalika Wada No. 3 Gautam Buddha Aa.Vi. ko paschim patti Budhi nadima tatbandhan nirman

IFB No.: 801055804/BMO/NCB/W/2083-84/6

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Supply, deliver, and install a standard-size project information board as per approved specifications. Provide and maintain all required insurances for the project duration, including Insurance of Works, Equipment, Contractor's Workmen/Employees, and Third-Party Liability against damage to persons and property. Carry out additional tests for materials and works as required and instructed by the Engineer. Provide a Provisional Sum for the operational and logistical expenses of the project management team (Project Manager, Site In-charge, Site Supervisor, and Monitoring Committee). This sum strictly covers actual information board, insurance,lab test, fuel and oil for site visits, vehicle maintenance, and miscellaneous administrative or meeting expenses. It shall be expense at the sole discretion of the Engineer. Reimbursement will be made on a remeasurement basis against genuine tax invoices and logbooks, with zero contractor profit or markup allowed."	PS	1.00	66,736.12 Sixty-six thousand seven hundred thirty-six rupees and twelve paisa only.	66,736.12 Sixty-six thousand seven hundred thirty-six rupees and twelve paisa only.
	Total provisional sums				66,736.12 Sixty-six thousand seven hundred thirty-six rupees and twelve paisa only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm, (for 10,000 sqm))	Sqm	180.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	90.00			
1.3	Supply of Machine Made Gabion boxes / mattresses with diapharagms including rolling, cutting and weaving as per specification. Including Providing and filling stone / boulder in gabion boxes / mattress etc. including dressing, beding, bonding and all transportation as per Specification.Hexagonal mesh type 100mmx120mm using hexagonal Mesh wire -3mm (0.0615 kg/m) & selvedge wire -3.9mm(0.1057kg/m) and Binding wire 12 SWG Box of different sizes as per requirements.	Cum	360.00			
1.4	Providing and laying of a geotextile filter between pitching and embankment slopes as per Drawing and Technical Specifications.	Sqm	180.00			
1.5	Providing suitable material and Back filling behind abutment, wing wall and return wall complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	558.00			

Total Item Price	
VAT (13.00%)	
Grand Total	