Bill of Quantities (BOQ)

Pakadi Purva Kulo dekhi Paschim Kulo samma Adhuro Baato Nirman, Mayadevi Ga Pa 1

IFB No.: 3370149015/02/RIDOKAP/10134/SQ/083-84/18

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Supply, place and maintain standard size 0.9 x 1.2 m sign board for Project information and Prepare and submit progress report/Final Report with Color prints in A4 size paper color photo and video.[110]	No.	1.00			
1.2	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300 mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable Material to be used or auctioned, up to a lead of 30 meters including removal and disposal of top organic soil not exceeding 150 mm in thickness. By Mechanical Means In area of light jungle (less than 15 number per 100 sqm, Unit = sqm,	Sqm	276.00			
1.3	Providing, laying, spreading, watering and compacting embankment with Roadway Cutting material in layers not exceeding 150mm including haulage as per drawing and Technical Specifications. (Mechanical Means)[909,910]	Cum	84.45			
1.4	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification (compacting orginal ground supporting embankment) [1003,1005]	Sqm	276.00			
1.5	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)[907]	Cum	5.98			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.[1000]	Cum	42.89			
1.7	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications[2000]	Cum	0.99			
1.8	Providing and laying Brick Masonry Work in Cement mortar (cement:sand 1:4) in Foundation/Structure complete excluding pointing, plastering etc all complete as per Drawing and Technical Specifications[2500]	Cum	6.30			
1.9	Providing and applying 12.5 mm thick Plaster with Cement mortar (cement:sand 1:4) on brickwork in structure as per Drawing and Technical Specifications[2500]	Sqm	15.20			
1.10	Providing and Laying RCC 600mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	5.00			
1.11	Providing and Laying RCC 300mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	5.00			
1.12	Providing and laying of PCC (Grade M 20) in foundation complete as per Drawing and Technical Specifications[2000]	Cum	41.40			

Total Item Price	
VAT (13.00%)	
Grand Total	