Bill of Quantities (BOQ)

Sita Paila Ghat Access Road Upgrading, Pokhara-17

IFB No.: 3370139024/NCB/W/R/405/2083-084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss of damage to works, plant,material,equipment property and personnel injury or death, including third party insurance as per Contract Document [GCC 19]	PS	1.00	25,000.00 Twenty-five thousand rupees only.	25,000.00 Twenty-five thousand rupees only.
PS.2	Relocation of Services and repairing for existing infrastructure (houses, water supply pipes, HDPE pipes, Electric Poles, Temple, Foot staircase, Foot trail etc) as instructed by engineer's. [SSRBW Clause 105]	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				35,000.00 Thirty-five thousand rupees only.

General Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Providing and installation of project signboards with size of 1m x1.2m (Board should be in Flex print with metal frame and both legs of the boards should be of black pipes with minimum diameter 1") as per instruction of Engineer.	Nos	1.00			

Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Compacting original ground supporting sub-grade Loosening of the ground upto a level of 500 mm below the sub-grade level, watered, graded and compacted in layers as per Drawing and Technical Specifications.	Sqm	557.44			

Construction Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.2	providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications. By Mechanical Means	cum	83.62			
2.3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M20 (Including Formwork, including cost of core cutting) all complete as per drawing and technical specification (SSRB 2000)	cum	111.49			
2.4	Providing and laying , fitting and placing HYSD bar reinforcement in sub-structure complete as per Drawing and Technical Specifications (SSRB 2014)	Kg	3,946.96			

Total Item Price	
VAT (13.00%)	
Grand Total	