Bill of Quantities (BOQ)

Chukhedhunga Simalkuna Sadak Staronnati, Birendranagar 11, Surkhet

IFB No.: 80668405300/2

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provide & install project information board in suitable place including 50mm dia. Steel tube, 2mm thick steel plate, cement concrete, painting, writing and supporting steel angle nut and bolt etc.all complete works (size 1.2 m × 0.9 m with back support)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
PS.2	Insurance of works , construction equipments & against to workmen including third party insurance against damage to other persons and property(clause 13 condition of contract)	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
PS.3	Material testing works as directed by Engineer.	PS	1.00	8,000.00 Eight thousand rupees only.	8,000.00 Eight thousand rupees only.
	Total provisional sums				38,000.00 Thirty-eight thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earth work in excavation of foundation of structures, including construction of shoring and bracing, removal of stumps and other deleterious matter and backfilling with approved Material as per Drawing and Technical Specifications. Ordinary soil by Mechanical means upto 3m depth	cum	323.19			
1.2	Stone filling in trench with proper leveling	cum	98.07			
1.3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. PCC Grade M 15 including formwork	cum	41.16			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications. RCC Grade M 20 including formwork.	cum	63.00			
1.5	Providing and laying , fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification	kg	6,389.185			
1.6	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications, 60% M 15 concrete and 40% boulders/stones, using Mechanical Aids	cum	83.16			
1.7	Using timber (soft wood), Providing , Preparing and Installing form work including necessary supports and removing after completion for walls.(Class F2 Finish), vertical plain surface Height upto 3 m	sqm	554.40			
1.8	providing of laying of Rcc Humpe pipe NP3 90mm hume pipe	Rm	5.00			
1.9	Providing, laying and spreading of loose natural sand gravel subbase grading as per table 12.1 of standard specification lead upto 10m. [Loose Gravel]	cum	87.30			

Total Item Price	
VAT (13.00%)	
Grand Total	