Bill of Quantities (BOQ)

Construction of Irrigation Canals and Procurement and Installation of HDPE Pipes in Different Toles of Parshuram -01, Dadeldhura.

IFB No.: 80775402300/04/WORKS/NCB/ PM/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation in Boulder mixed and Soft soil in foundation, trenches including timbering and shoring & 30m Lead and 1.5 m. lift all complete as per design, drawing and specification.	Cu.m	23.95			
1.2	Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification.	Cu.m	29.28			
1.3	P.C.C.(1:2:4) for P.C.C.work in foundation, columns, beams, slabs, lintels etc. with cement, sand, and crushed stone aggregate of size less than 20mm including mixing with concrete mixture, compacting the concrete with vibrator machine, laying, finishing to approved level ,lines and dimensions and curing all complete nett.	Cu.m	37.32			
1.4	Formwork with approved materials for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Column/Slab/Beam etc. complete work	Sq.m	120.62			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Steel reinforcement bar (grade 415 or above) tested including straightening, cleaning, cutting, bending and fixing in position with 20 B. G. annealed binding wire as per drawing and instruction complete work	kg	811.71			
1.6	Stonework in cement sand (1:6) mortar in foundation with random rubble stones of approved size and quality including wetting the stones, packing the joints and curing the works in all types and thickness of walls all complete work.	cum	1.08			
1.7	Procurement Supply laying & testing of HDPE pipe of Nepal Standard good quality as per employer requirements all complete works.	Kg	567.00			
1.8	Supply and Installation of Miscellaneous Fittings (GI Pipes for Inlet, Outlet, Washout, Overflow, End Caps, etc.) Required for Completion of Works.	LS	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	