Bill of Quantities (BOQ)

Construction and Upgrading of Branch Roads in Different Toles of Parshuram -07, Dadeldhura

IFB No.: 80775402300/02/WORKS/NCB/ PM/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

Construction work **CPV: 45000000-7 - Construction work**						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Earthwork in excavation in hard/boulder mix soils in foundation including 10m hauling distance and 1.5 m. lift all complete.	Cum	252.15			
1.2	Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification.	Cum	1.80			
1.3	Providing and laying of plain cement concrete M 15 (1:2:4 for nominal mix) in foundation as per drawing and technical specification.	Cum	1.20			
1.4	Providing and laying the natural gravel on prepared surface all complete as per drawing and technical specifications.	Cum	421.88			
1.5	Providing, mixing with mixer machine, laying , compacting with vibrator and curing plain cement concrete M20 (1:1.5:3) for foundation, coloumn, slab, beams, tie beam Lintel Sill and all kinds of R.C.C. works with cement sand and crushed stone aggregate 20mm down finishing to approved level lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cum	11.84			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.6	Steel reinforcement bar (grade 415 or above) tested including straightening, cleaning, cutting, bending and fixing in position with 20 B. G. annealed binding wire as per drawing and instruction complete work	Kg	1,079.58			
1.7	19 mm waterproof plywood and wooden prop formwork for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization	Sqm	75.22			
1.8	Providing and fixing 40 mm dia MS pipe railing for Culvert Including cutting ,welding , fabrication erection one Coat of anti-corrosive primer and two coats of enamel paint complete in all respects per appobed drawing and specification.	Kg	202.92			

Total Item Price	
VAT (13.00%)	
Grand Total	