Bill of Quantities (BOQ)

Infrastructure development from Shivalal's house to Gairawari Saurarukh, Dhurkot-7, Construction of a concrete-paved stepped path from Jimmal to Pallar, Dhurkot-7 and Construction of urban infrastructure from Khanal ko Chaur, via Syalti, to Gahate, D

IFB No.: 3470150015/UDBOP-NCB-083/84-19

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance premium for the work, plant and materials damage for contract work for the insurance of owner and consultant staff (named); Insurance Premium for construction equipments and machines; Insurance Premium for third party liability personal only	PS	1.00	25,017.00 Twenty-five thousand seventeen rupees only.	25,017.00 Twenty-five thousand seventeen rupees only.
PS.2	Material Tests	PS	1.00	5,424.00 Five thousand four hundred twenty-four rupees only.	5,424.00 Five thousand four hundred twenty-four rupees only.
PS.3	Supply and Place standard size sign board for Construction Information	PS	1.00	3,000.00 Three thousand rupees only.	3,000.00 Three thousand rupees only.
	Total provisional sums				33,441.00 Thirty-three thousand four hundred forty-one rupees only.

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	cum.	327.38			
1.2	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto	cum.	31.46			

Road construction works
CPV: 45233120-6 - Road construction works

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Road way Excavation in all types of soil as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per Drawing and instruction of the Engineer. (mechanical means)	cum.	26.10			
1.4	Providing and laying of hand pack Stone soling with stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	cum.	81.11			
1.5	Providing and laying plain Cement Concrete PCC(Grade M15) Including batching , mixing, transporting,placing,,compactiing,finishing,curing and formwork wherever required,complete in accordance with the approved drawings, DOR Standard Specifications and instructions of the Engineer	cum.	24.99			
1.6	Providing and Pointing with cement mortar (1:3) on masonry work in structure as per Technical Specifications	sqm	52.80			
1.7	Construction of stone masonry for Retaining walls/drains in 1:4 cement-sand mortar with 4" HDP pipe weap hole including supply of materials, curing all complete.	cum.	49.86			
1.8	Providing and laying Plum concrete (Boulder mixed concrete) as per Drawing and Specifications 60% M 15 concrete and 40% Boulders/stones Mechanically with formwork .	cum.	11.60			
1.9	Providing and laying Reinforcement Cement Concrete RCC(Grade M20) in footing, columns,beams,slabs,lintels and other structural members Including batching , mixing, transporting,placing,vibrating, compactiing,finishing,curing ,complete as per approved drawing,technical Specifications and instructions of the Engineer	cum.	57.22			
1.10	Supplying,cutting,bending and fixing high yield deformed reinforcement steel including binding wire chairs spacers laps and all incidental works complete in accordance with the approved drawing DOR Standard Specifications and instructions of the Engineer	kg	1,883.70			

Total Item Price	
VAT (13.00%)	
Grand Total	