Bill of Quantities (BOQ)

Upgrading of Pasewan Gaushara Tamchet Sadak

IFB No.: 801032406/DSRM/Works/NCB/083/84-02

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance of works, plants, materials, loss and damage to equipments, Contractor's workmen and employees and third party insurance against damage to other persons and property.for project period + DLP Period	PS	1.00	82,545.00 Eighty-two thousand five hundred forty-five rupees only.	82,545.00 Eighty-two thousand five hundred forty-five rupees only.
PS.2	Provide and installation of project information board of size 1.80 m X 1.2 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.Provisional Sum	nos	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				92,545.00 Ninety-two thousand five hundred forty-five rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Roadway excavation in all types of soil by mechanical means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as drawing and instruction of engineer.	cu.m	23,895.104			
1.2	Roadway Excavation in ordinary rock as per Drawing and Technical specification, including all lift and lead as per Drawing and instruction of the Engineer.	cu.m	2,906.565			
1.3	Roadway excavation in hard rock with rock breakers, including breaking rock lifts and lead for disposal as per drawing and technical specification, mechanical lead upto 30 m.	cu.m	2,539.859			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing mechanically woven double twisted crates / mattress(Heavy Zinc coated Hexagonal mesh type 100X120 mm, mesh wire 3 mm, selvedge wire 3.90 mm, lacing wire 2.40 mm) including rolling cutting and with lacing wire and binding wire and filling stone/boulder in gabion boxes/mattress etc. including dressing, bedding, bonding all complete as per drawing and technical specification	cu.m	68.00			
1.5	Providing and Laying of a Geo-Textile filter/geo membrane between pitching and embankment slopes,behind earth retaining structures as per drawing and Technical specification	sqm	40.00			
1.6	Providing and laying of hand packed stone solling with 150 to 200 mm thick stones and packing with smaller stones on prepared surface as per drawing and technical specifications.	cu.m	160.00			

Total Item Price	
VAT (13.00%)	
Grand Total	