Bill of Quantities (BOQ)

Babai hattikhal geruwani ghuiyawari salyan sadak starunnati, Bheriganga 5

IFB No.: 801066803/BGM/IDB/NCB/2083/084-04

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's staff, personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract. [GCC Clause]	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
PS.2	Carrying out different laboratory tests of during entire construction period as per specification and instruction of engineer	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
	Total provisional sums				70,000.00 Seventy thousand rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density, complete as per Drawing and Technical Specifications., By Mechanical means	cum	9.60			
1.2	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of sub-base/Base course as per Drawing and Technical Specifications., By Mix in Place Method	cum	370.50			
1.3	Prime Coat, Prime Coat, with MC 30 / 70 by Mechanical Means, Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical Specification ., Bitumen (cutback) MC 30 (for stabilized soil base/ crusher run macadam)	ltr	2,223.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Tack Coat, Tack coat with Bitumen By Mechanical Means, Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation .	ltr	1,235.00			
1.5	Bituminous Concrete / Asphalt Concrete, Providing and laying Bituminous concrete/ Asphalt concrete using crushed aggregates of specified grading, premixed with bituminous binder and filler as per Drawing and Technical Specifications, Grading - I-19 mm (Nominal Size)	cum	98.80			
1.6	Providing and laying of hot applied thermoplastic compound at least 2mm thick including reflectorizing glass beads asper DOR Traffic sign manual/ Specifications. The finished surface to be level, uniform and free from streaks and holes. SS 1504	sqm	154.375			
1.7	Providing and installation of project signboards with size of 1.8 x 1.2 m as per specification and instruction of engineer.	Nos	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	