Bill of Quantities (BOQ)

Construction of Irrigation Canals and Procurement and Installation HDPE Pipes in Different Toles of Parshuram -08, Dadeldhura.

IFB No.: 80775402300/03/WORKS/NCB/ PM/2083/084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Provisional Sum	PS	1.00	0.00 Zero rupees only.	0.00 Zero rupees only.
	Total provisional sums				0.00 Zero rupees only.

Construction work
CPV: 45000000-7 - Construction work

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Earthwork in excavation in Boulder mixed and Soft soil in foundation, trenches including timbering and shoring & 30m Lead and 1.5 m. lift all complete as per design, drawing and specification.	Cu.m	68.61			
1.2	Stone soling work in foundation and floors with supplying of approved quality of stone laying, ramming and levelling including filling in the joints with sand as per design, drawing and specification.	Cu.m	28.80			
1.3	P.C.C.(1:2:4) for P.C.C. and RCC work in foundation, columns, beams, slabs, lintels etc. with cement, sand, and crushed stone aggregate of size less than 20mm including mixing with concrete mixture, compacting the concrete with vibrator machine, laying, finishing to approved level ,lines and dimensions and curing all complete nett.	Cu.m	48.88			
1.4	Steel reinforcement bar (grade 415 or above) tested including straightening, cleaning, cutting, bending and fixing in position with binding wire as per drawing and instruction complete work	Kg	219.39			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.5	Formwork with approved materials for all works necessary propping, scaffoldong, staging, supporting inclusive of wedging and cutting holes for utilization work till the support is full unyielding nett for Column/Slab/Beam etc. complete work	Sq.m	144.30			
1.6	Inistallation And Procurement Of HDPE Pipe Of Nepal Standard	Kg	695.16			
1.7	Inistallation and Procurement of Tochen Wire rope of 12mm for tallo kulo rcc dhalan kareni	rm	40.00			

Total Item Price	
VAT (13.00%)	
Grand Total	