Bill of Quantities (BOQ)

Pashupati Ma.Vi. Adhuro Bhawan Nirman

IFB No.: RRM/2083-84/NCB/Works/05

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Insurance for the loss or damage to works,pant,material, equipment,property and personnel injury or death and third party as per contract data including mobilization ,demobilization expenses for manpower,equipment and performance bond commision. Contractor's workmen and employees and Third party Insurance against damage to other persons and property.	PS	1.00	30,000.00 Thirty thousand rupees only.	30,000.00 Thirty thousand rupees only.
PS.2	Dismentaling and Petty Repair Works as specified and instructed by site engineer.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.3	Supplying & Fitting of necessary electrical accessories items all complete for as specified by site engineer.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.4	Additional Lab Test as specified and instructed by site engineer.	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
	Total provisional sums				45,000.00 Forty-five thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Project Information Board as specified and instructed by Site Engineer.	Nos.	1.00			
1.2	E/W Excavation for Foundation	Cum	1.92			
1.3	Broken Brick Soling Works in foundation as per Drawings and Technical Specification	Cum	12.40			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.4	Providing and laying of PCC (Grade M 10) in foundation as per Drawing and Technical Specifications	Cum	0.48			
1.5	Brick Masonry Works in 1:6 c/s mortar	Cum	2.89			
1.6	Flooring Works:Transported Earth Filling Works with Compaction	Cum	58.13			
1.7	Flooring Works:Providing and laying of PCC (Grade M 15) as per Drawing and Technical Specifications	Cum	17.47			
1.8	12.5 mm 1:4 c/s Cement Plastering Work	Sqm	972.52			
1.9	Flooring Works:3mm Neat Cement Punning Works	Sqm	406.37			
1.10	Metal Works for Doors & Windows Frame , Shutter and Grill Fitting & Supply all Complete	Kg	2,089.00			
1.11	Metal Works :- Collapsible Gate Supply and Fitting all Complete.	Sqm	4.72			
1.12	Enamel Paint Followed by Primer in First Floor & Second Floor (Doors & Windows)	Sqm	98.56			
1.13	Stainless Steel Railing Works with 2" dia top, 1.5" dia middle and bottom pipe in 4 rows total, 2" dia posts at ~1m c/c finish clear height including the cost of materials and labour and fixing and ftting all complete.	Rm	14.70			
1.14	Supply and fabrications of 25*25*1.8 mm square pipe made Fiber Desk (Size:- 14"*30"*72") and Bench (Size:- 10"*18"*72") with fiber cover on top and desk having bag holding layer.	Set	7.00			
1.15	2*3/20 pvc cu.wire for light and fan point in 1/2" HDPE pipe including accessories: HDPE polyethene pipe, screws,PVC tape,grips,Circular box ,etc. all complete.	Point	72.00			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.16	2*7/22 +1*3/22 pvc. wire for power point in 3/4" HDPE pipe including accessories: HDPE polyethene pipe, screws,PVC tape,grips,Circular box ,etc. all complete.	Point	10.00			
1.17	LED 12 Watt Light	Set	40.00			
1.18	48" Ceiling Fan Usha/Equivalent including accessories: Regulator,Nut Bolt,Hook,Clamp,Flexible Wire,etc. all Complete.	Set	32.00			
1.19	6 gang 1,2 way Switch including accessories: Metal Box,Screw,Grips,PVC Tape,etc. all Complete.	Set	10.00			
1.20	16 Amp Power Socket including accessories: Metal Box,Screw,Grips,PVC Tape,etc. all Complete.	Set	10.00			
1.21	Distribution Board 8 Way TPN made of Mild Steel Sheet double cover locable of approved company.Flush type etc .all complete including accessories: Screw,grips,nut,bult,cu bus bar,earth bus bar,neutral bus bar,fuse,procelin base,cu strip for connectionn,cable shoe,phase bar,pvc tape etc all complete.	Set	2.00			
1.22	16 amps TP MCB of approved company for main including accessories: Screw,grips,nut,bult,cu bus bar,earth bus bar,neutral bus bar,fuse,procelin base,cu strip for connectionn,cable shoe,phase bar,pvc tape etc all complete.	Nos	16.00			
1.23	Earthing with cu. plate size 65cm*65cm*3.1smm with G.N.B copper wire for earth continuity from panel board to earthing site etc. all complete.	Unit	1.00			

Total Item Price	
VAT (13.00%)	
Grand Total	