Bill of Quantities (BOQ)

Upgrading Of Raharpur Dekhi Kopila Ma. Bi. Jodne Sadak ward No.10, Surkhet.

IFB No.: 3370168016/02-IDO/SKT/W/NCB/15/083-084

Provisional Sum

SL. No.	Item Description	Unit	Quantity	Unit Rate (NPR)	Amount (NPR)
PS.1	Insurance for the loss or damage to works, plant, material, equipment, property, Contractor's employees and labour, Employer's and Consultants's staff personnel injury or death and third party property and persons during the construction period and upto the end of defects liability period as per the condition of contract.	PS	1.00	45,000.00 Forty-five thousand rupees only.	45,000.00 Forty-five thousand rupees only.
PS.2	Carry out additional tests for material and works as required and instructed by the Project Manager.	PS	1.00	32,000.00 Thirty-two thousand rupees only.	32,000.00 Thirty-two thousand rupees only.
PS.3	Relocation of electric poles, water supply lines etc all complete.	PS	1.00	2,30,000.00 Two lakh thirty thousand rupees only.	2,30,000.00 Two lakh thirty thousand rupees only.
	Total provisional sums				3,07,000.00 Three lakh seven thousand rupees only.

General Item

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.1	Provide and installation of project information board of size 1.2 m X 0.9 m along with iron posts including excavation, concreting,backfillingetc all complete as per DoR Standard Specifixcation for Road and Bridge Works.	No.	1.00			

Pavement Works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
2.1	Scarifying Existing road Surface to a depth 50 mm and disposal of scarified material with in all lifts and lead as per Drawing and Technical Specifications.	sqm	1,980.50			
2.2	Providing and laying Crusher Run Macadam on a prepared surface, spreading and mixing , watering and compacting to form a layer of Base course as per Drawing and Technical Specifications. all complete.	Cum	297.07			
2.3	Prime Coat, Prime Coat, with MC 30 / 70 by Mechanical Means, Providing and applying prime coat with Hot Bitumen (including cutter) on prepared surface of granular base including cleaning of road surface and spraying by mechanical means as per Technical Specification ., all complete.	ltr	1,584.40			
2.4	Tack Coat, Tack coat with Bitumen By Mechanical Means, Providing and applying tack coat with hot Bitumen at specified rate on the prepared non-bituminous surfaces including cleaning as per Technical Speciation., all complete.	ltr	1,134.37			
2.5	Providing and laying bituminous concrete/asphalt concrete using crushed aggregate of specified grading, premixed with bituminous binder and filler as per drawing and technical specification.	Cum	60.50			

Total Item Price	
VAT (13.00%)	
Grand Total	