Bill of Quantities (BOQ)

Construction of Boundary Wall of Shree Janta Adarsh Ma. Vi. Baijnath- 02 Jabdhwa , Banke

IFB No.: 3500057025/SDDOBANKE/W/NCB-08/2083/084

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supplying and erecting 1.5m.x 1.2m. size Project Sign Board in place including 50mm dia. Steel tube, 2mm. thick steel plate, cement concrete, painting, writing and supporting steel angle nut and bolit etc. all complete	PS	1.00	5,000.00 Five thousand rupees only.	5,000.00 Five thousand rupees only.
PS.2	Carrying out diferrent laboratory tests of construction material like rod, bricks & concrete cubes etc. during construction work as per specification and direction.	PS	1.00	10,500.00 Ten thousand five hundred rupees only.	10,500.00 Ten thousand five hundred rupees only.
PS.3	Insurance premium for the work, plant and materials damage for the contract work for all risk including riot, strike, damage, malicious damage and terrorism for contract work of accepted amount for 15 months +1 year maintainance period.	PS	1.00	20,000.00 Twenty thousand rupees only.	20,000.00 Twenty thousand rupees only.
	Total provisional sums				35,500.00 Thirty-five thousand five hundred rupees only.

Education and training services CPV: 80000000-4 - Education and training services						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Clearing the site for stacking the useful items in specified space and disposing other item before commencing the construction work as per instruction of the site engineer all complete including layout of buildings, roads and ancillary services.	Sq.m	74.50			
1.2	Earthwork in excavation in medium type soils in foundation including 10m hauling distance and 1.5 m. lift all complete in approval of site engineer.	Cu.m	47.55			

Education and training services
CPV: 80000000-4 - Education and training services

SL. No.	Item Description	Unit	Quantity	Bidder's Rate (NPR)	Bidder's Rate (in words)	Total Amount (NPR)
1.3	Providing & laying Stone soling in foundation & floor including voids filling with sand all complete as per instruction of the site engineer.	Cu.m	5.97			
1.4	Providing, laying, compacting and curing plain cement concrete M10 (1:3:6) in foundation with cement, sand and stone ballast 20mm gauge finishing to approved level, lines and dimensions all complete as per drawings, specifications and instruction of the site engineer.	Cu.m	4.48			
1.5	Providing, laying, compacting and curing M20 (1:1.5:3) plain cement concrete for column, slab, beams, tie beam Lintel Sill and all kinds of R.C.C. works with opc 43grade minimum cement sand and stone ballast 20mm down finishing to approved level, line and dimensions using mixer machine & vibrator all complete as per specifications, drawings and instructions of the site engineer, all complete	Cu.m	17.21			
1.6	Providing formworks for wall constructionworks as per specification, drawing & instruction of site engineer.	Sq.m	203.25			
1.7	Reinforcement bars (Fe 500 TMT) work including straightening, cleaning, cutting, bending, binding with 20 SWG annealed wire & fixing in position as per drawing, bar bending schedule for raft foundation column, beam, wall, stair, slab in all R.C.C. works as per specification, drawing & instruction of site engineer. Approved brands: Himal Iron, Panchakanya or equivalent.	K.g	1,946.08			
1.8	Providing, laying and curing first class brick masonry works in cement, sand mortar (1:4) in substructure, ground floor finished in perfect lines & level as per specification, drawings & instructions of the site engineer.	Cu.m	48.56			
1.9	Providing, laying & curing 12.5 mm thick cement sand (1:4) Plastering on outside wall to perfect plumb, lines & level all complete as per design drawings, specifications and instruction of the site engineer all complete:	Sq.m	586.12			

Education and training services CPV: 80000000-4 - Education and training services						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.10	Supplying and applying Two coat weather proof painting (Apex or equivalent) with One coat of cement primer of approved colour in outer side of building as per specifications and instruction of the site engineer.	Sq.m	586.12			
1.11	Providing and fabricating grill with solid square M.S. rod strips and angle of approved pattern and manufacture finished with one coat of metal primer and enamel paint with approved colour as per design, drawing and instruction all complete.	K.g	1,455.98			

Total Item Price	
VAT (13.00%)	
Grand Total	