Bill of Quantities (BOQ)

Road Improvement Works with RCC Slab from Head pond to Khanikhola Intake-Phase 1 of KL3HPS

IFB No.: 151422/NEA-KL3-2083/084-CST-01

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Providing and conducting necessary laboratory test for the Concrete specimen and Core cutting of RCC work as per approved specification and instructions of site Engineer	PS	1.00	40,000.00 Forty thousand rupees only.	40,000.00 Forty thousand rupees only.
	Total provisional sums				40,000.00 Forty thousand rupees only.

Rigid Pavement works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Road way Excavation in all types of soil by Mechanical Means as per Drawing and technical specifications including removal of stumps and other deleterious matter, all lifts and lead as per instruction of the Engineer.	Cum	113.60			
1.2	Dry stone soling in foundation, floor including supply of materials & haulage distance up to 30 m	Cum	85.20			
1.3	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Technical Specifications. RCC Grade M20	Cum	85.20			
1.4	Providing and laying, fitting and placing un-coated Mild steel / HYSD reinforcement complete in foundation as per drawing and technical specification	Mt	3.51			
1.5	Formwork with 19mm thick waterproof ply board for Panel partition	Sqm	14.20			
1.6	Procurement and supplying of HDPE pipe for Draining Water,110mm dia 6kg/cm2 (PN 10)	kg	139.73			

Rigid Pavement works						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.7	Providing suitable material and Back filling behind abutment, wing wall, return wall and road side complete as per drawing and Technical Specifications. (Mechanical Means)	Cum	25.56			

Total Item Price	
VAT (13.00%)	
Grand Total	