Bill of Quantities (BOQ)

5no. ward gravel package

IFB No.: 801055804/BMO/NCB/W/2083-84/7

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Supply, deliver, and install a standard-size project information board as per approved specifications. Provide and maintain all required insurances for the project duration, including Insurance of Works, Equipment, Contractor's Workmen/Employees, and Third-Party Liability against damage to persons and property. Carry out additional tests for materials and works as required and instructed by the Engineer. Provide a Provisional Sum for the operational and logistical expenses of the project management team (Project Manager, Site In-charge, Site Supervisor, and Monitoring Committee) as well as petty civil and miscellaneous items.. This sum strictly covers actual fuel and oil for site visits, vehicle maintenance, and miscellaneous administrative or meeting expenses. It shall be expense at the sole discretion of the Engineer. Reimbursement will be made on a remeasurement basis against genuine tax invoices and logbooks, with zero contractor profit or markup allowed."	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				10,000.00 Ten thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.1	Scarifying, looseing , Reshaping and compaction of existing gravel layer of the road and removal of over size gravel.	SQM	9,153.00			
1.2	Roadway and drain excavation in all types of Soil by Mechanical Means as per drawing and technical specification, including removal of stumps and other deleterious matter, with all lifts and lead as per Drawing and instruction	CUM	205.36			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Construction of Embankment with Material obtained from borrow pit. Providing, laying, spreading and compacting embankment with borrow pit material.	CUM	182.38			
1.4	Screenig, Supply,Transportation & laying re-gravelling material over the existing River Bed sub-base material max. 50 mm down including application binding material spreading,watering and machanical compaction with cambering and other incidential all comple	CUM	416.32			
1.5	Providing and Laying RCC 450mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	RM	7.50			
1.6	Providing, laying and levelling of dry stone soling works in the foundation all complete.	CUM	0.68			
1.7	Providing and laying of PCC (Grade M 10) in foundation complete as per Drawing and Technical Specifications	CUM	0.72			

Total Item Price	
VAT (13.00%)	
Grand Total	