Bill of Quantities (BOQ)

Upgrading of Milijuli path kha line Ganeshtole Butwal-12, Rupandehi

IFB No.: 3370148025/RIDO/RUP/134/NCB/083-084/96

Provisional Sum					
SL. No.	**Item Description**	**Unit**	**Quantity**	**Unit Rate (NPR)**	**Amount (NPR)**
PS.1	Relocation of services / minor infrastructures, as per specifications and instruction of the Engineer.(SS/SP-109)	PS	1.00	10,000.00 Ten thousand rupees only.	10,000.00 Ten thousand rupees only.
	Total provisional sums				10,000.00 Ten thousand rupees only.

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.3	Insurance for the loss of damage to works, plant, material, equipment property and personnel injury or death, including third party insurance as per Contract Document (SS/SP-117)	LS	1.00			
1.4	Provide and Installation of project signboards as per specification and instruction of engineer.(SS/SP-110)	Nos.	1.00			
1.5	Scarifying the existing road surface by to a depth of 50 mm and disposal of scarified material with all lifts and leads as per Drawing and Technical Specification.	Sqm	1,453.50			
1.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as drawings and technical specifications.@ Depth upto 3m (mechanical means)	Cum	69.85			
1.6	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	Cum	38.47			

Construction work CPV: 45000000-7 - Construction work						
SL. No.	**Item Description**	**Unit**	**Quantity**	**Bidder's Rate (NPR)**	**Bidder's Rate (in words)**	**Total Amount (NPR)**
1.7	Providing and laying of Plain/Reinforced Cement Concrete in Foundation complete as per Drawing and Technical Specifications, PCC Grade M 15 including formworks	Cum	25.98			
1.8	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including pipes for weep holes etc all complete as per Drawing and Technical Specifications. (Mechanical Means)	Cum	68.85			
1.9	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	cum	218.02			
1.10	RCC Grade M25/20 Providing and laying of ready mix reinforced cement concrete using batching plant, transit mixer, concrete pump, admixtures, etc. all complete as per drawing and technical specification	Cum	21.62			
1.11	Providing and Laying RCC 300mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	15.00			

Total Item Price	
VAT (13.00%)	
Grand Total	